

**WATER PERMIT NO. 8731-3**

Name of Applicant: **Gary Stapelman**

Address: **724 E Shadow Creek Ln, Sioux Fall SD 57108**

Phone: **402-709-7132**

Amount of Water Claimed: **1.67 cfs**

Total Acres: **162**

Source of Water Supply: **Groundwater**

Water to be used for: **Irrigation**

County: **Clay**

Type of Waste Disposal System:

Location: **9 miles north of Vermillion**

**PRIORITY**

Date Received: **3-15-2023**

Application/License Fee: **\$1,050.00**

Corrected Application Received:

Period of Annual Use: **May 1 – Sept 30**

Remarks:

Diversion Point: **Center SW 1/4 Sec 3 – T93N – R**  
**51W**

Land to be Irrigated: **SW 1/4 Sec 3 – T93N –**  
**R51W**

Depth of Well: **200**

Well Driller:

Remarks:

Type of Map: **aerial**

|  |  |  |   |  |  |
|--|--|--|---|--|--|
|  |  |  |   |  |  |
|  |  |  |   |  |  |
|  |  |  | 3 |  |  |
|  |  |  |   |  |  |

Reviewed and the Number Assigned on: **3-15-2023**

By: **Karen Schlaak**

Notice of Hearing - date to intervene: \_\_\_\_\_

**SOUTH DAKOTA  
WATER PERMIT NO. 8731-3**

---

Date of first receipt of application March 15, 2023.

The Chief Engineer, on behalf of the Water Management Board, issues Water Permit No. 8731-3 to Gary Stapelman, 724 E Shadow Creek Ln, Sioux Falls SD 57108 authorizing the construction of the water use system and the placing of water to beneficial use subject to the following limitations, conditions and qualifications:

1. Water Permit No. 8731-3 appropriates 1.67 cubic feet of water per second (cfs) from one well to be completed into the Lower Vermillion Missouri Aquifer (approximately 200 feet deep) located in the approximate center of SW 1/4 Section 3 for irrigation of 162 acres located in the SW 1/4 Section 3; all in T93N-R51W. This site is located approximately 9 miles northeast of Vermillion SD.
2. The amount of the appropriation may not exceed 2 acre feet annually for each acre of land to which water is actually and beneficially applied for irrigation. The water is to be used during the following described annual period: May 1 – September 30.
3. The date from which applicant may claim right is March 15, 2023.
4. The date of approval of Permit No. 8731-3 is June 12, 2023.
5. One-fifth of the construction is to be completed on or before December 12, 2025.
6. All construction is to be completed on or before June 12, 2028.
7. Water is to be put to beneficial use on or before June 12, 2032.
8. Water rights obtained in compliance with the laws of the State of South Dakota may not be unlawfully impaired by this appropriation.

**QUALIFICATIONS**

1. The well approved under Water Permit No. 8731-3 is located near domestic wells and other wells which may obtain water from the same aquifer. Water withdrawals shall be controlled so there is not a reduction of needed water supplies in adequate domestic wells or in adequate wells having prior water rights.
2. The well authorized by Permit No. 8731-3 shall be constructed by a licensed well driller and construction of the well and installation of the pump shall comply with Water Management Board Well Construction Rules, Chapter 74:02:04 with the well casing pressure grouted (bottom to top) pursuant to Section 74:02:04:28.
3. This Permit is approved subject to the irrigation water use questionnaire being submitted each year.

**WATER MANAGEMENT BOARD**

By: Eric Gronlund  
Eric Gronlund, Chief Engineer  
Water Rights Program  
Department of Agriculture and Natural Resources

JUL 11 2023  
date



**FORM 2: Application for irrigation in South Dakota**  
(type or print)

|                                                                                                               |                                                                                                                                                                                        |
|---------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Mail to:<br><br>SD DANR, Water Rights<br>523 E Capitol Ave<br>Pierre, SD 57501-3182<br><br>ph. (605) 773-3352 | No. <u>8731-3</u> Hydrologic Unit <u>10170102</u><br>Basin <u>Vermillion River</u><br>Newspaper <u>Plain Talk 624-2695</u><br><u>Press &amp; Dakotan 605-7811</u><br>(office use only) |
|---------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

**PAID**  
MAR 15 2023  
Ck# 6203  
Rec't# \_\_\_\_\_  
**RECEIVED**

**Application for Permit to Appropriate Water for Irrigation**

MAR 15 2023

Type of Application: ☒ New ☐ Vested Right ☐ Amendment/Correction to Permit No. \_\_\_\_\_  
(Use predates Mar 2, 1955) **OFFICE OF WATER**

Description of amendment/correction: (i.e. change diversion point(s), add diversion point(s), change use, etc.)

1. Name to Appear on Irrigation Permit Gary Stapelman  
**Note:** The "Name to Appear on Irrigation Permit" must be the name in which the property to be irrigated is held in.  
Mailing Address 724 E Shadow Creek Ln Sioux Falls SD 57108  
(Address) (City) (State) (Zip Code)  
Phone \_\_\_\_\_ Mobile 402-709-7132 Email debstapelman51@gmail.com  
2. Amount of water claimed \_\_\_\_\_ \*CFS or 750 \*\*GPM \_\_\_\_\_ \*\*\*AF Total Acreage 162  
(\*Cubic Feet per Second) (\*\*Gallons per Minute) (\*\*\*)Acre Feet - storage capacity of dam/dugout or annual use if applicable)  
3. Source of water supply Irrigation Well (1)  
4. Location of point of diversion Center of Quarter SW 1/4 Section 3 T-93-N  
(example - 3 wells in SW1/4 NE1/4 section 12-T104N-R53W)  
R-S1-W County CLAY  
5. County or counties where water will be used CLAY  
6. Annual period during which water is to be used MAY - Sept. 30  
7. List below each forty-acre division, or lot, or fraction thereof and show number of acres to be irrigated in each.  
(Attach sheet if more space is needed)

| Land Description | Acres | Land Description | Acres |
|------------------|-------|------------------|-------|
| NESW             | 40.5  |                  |       |
| SESW             | 40.5  |                  |       |
| SWSW             | 40.5  |                  |       |
| NWSW             | 40.5  |                  |       |

Section 3, T93N  
R-S1-W  
CLAY County

8. Give a description of the project. (Attach sheet if more space is needed)

Drill a well in center of the quarter & put up a center pivot.

I, Gary Stapelman, the applicant, certify under  
Name of Person Title (if applicable)

penalty of perjury that I have read this application, examined the attached map, and that the matters stated are true. I further certify, if acting on behalf of an entity or individual other than myself, that I am authorized to submit this application.

## Supplemental Information

(type or print)

### 1. Well Information (check one or both as applicable)



Drilling new well(s)



Using existing well(s)

a) If new wells, how many \_\_\_\_\_ Have test holes been drilled? ☐ Yes ☒ No Drilled by \_\_\_\_\_  
(if yes, please provide copies of logs)

b) If existing wells, how many \_\_\_\_\_ Provide copy of log(s), if available. Drilled by \_\_\_\_\_

#### For either existing or proposed wells:

c) Well Depth (required) 200 Depth to Top of Water Bearing Material 90 Depth to Water from Surface 90

d) Distance to nearest domestic well on applicant's property — Property owned by others 3400

### 2. Wastewater Disposal System Information

a) Type of System (i.e. septic tank, drain field) \_\_\_\_\_

b) System Capacity (gallons) \_\_\_\_\_ Year Constructed \_\_\_\_\_

c) Connected to the City of \_\_\_\_\_ Sanitary System

### 3. Dugout Information

a) Surface Dimensions \_\_\_\_\_ Depth \_\_\_\_\_

b) Depth to water (ground surface to water level) \_\_\_\_\_

### 4. Water Storage Dams

If the proposed water use system contains one or more storage dams, please furnish the information requested below for each dam. The locations of the dams need to be shown on the map submitted with the application.

a) If a private engineering firm or government agency was involved in the design of this dam, please give their name and address:

b) Freeboard \_\_\_\_\_

c) Crest Width \_\_\_\_\_

Crest Length \_\_\_\_\_

d) Height \_\_\_\_\_

e) Primary Outlet Capacity \_\_\_\_\_

If pipe, diameter \_\_\_\_\_

f) Secondary Spillway Capacity \_\_\_\_\_

Spillway Width \_\_\_\_\_

g) X & Y Slope (e.g. 3 to 1 is a typical slope)


Upstream \_\_\_\_\_

Downstream \_\_\_\_\_

h) Area of Impoundment \_\_\_\_\_

i) Storage \_\_\_\_\_ Acre Feet

j) Drainage Area Above Dam \_\_\_\_\_ Acres



# Untitled Map

Write a description for your map.

## Legend *Stapelman*

-  Gary Stapelman new well site SW 1/4 S3 T-93-N R51W Clay
-  Measure
-  Polygon Measure

Gary Stapelman new well site SW1/4 S3 T-93-N R51W Clay 

310th St

310th St

310th St

Google Earth

1000 ft



8731-3


SD EForm - 1621LD V1

## SOUTH DAKOTA WATER WELL COMPLETION REPORT

11-02

Location NE 1/4 SW 1/4 Sec 3 Twp 93-N Rg 51-WCounty Clay

Please mark well location with an "X"



Well Completion Date

5-24-23

1 Mile

Distance to nearest potential pollution source (septic tank, abandoned well, feed lot, etc.)?

2900 ft. from Septic Tank (identify source)

## PROPOSED USE:

☐ Domestic/Stock ☐ Municipal ☐ Business ☐ Test holes  
☒ Irrigation ☐ Industrial ☐ Institutional ☐ Monitoring well

## METHOD OF DRILLING:

Reverse Rotary

## CASING DATA:

☐ Steel ☒ Plastic ☐ Other

If other describe

| PIPEWEIGHT       | DIAMETER      | FROM        | TO          | HOLE DIAMETER    |
|------------------|---------------|-------------|-------------|------------------|
| <u>160</u> LB/FT | <u>16"</u> IN | <u>0</u> FT | <u>0</u> FT | <u>18 1/2</u> IN |
| LB/FT            | IN            | FT          | FT          | IN               |
| LB/FT            | IN            | FT          | FT          | IN               |

## GROUTING DATA:

| Grout Type    | No. of Sacks | Grout Weight    | From        | To           |
|---------------|--------------|-----------------|-------------|--------------|
| <u>Cement</u> | <u>215</u>   | <u>0</u> Lb/gal | <u>0</u> Ft | <u>95</u> Ft |
|               |              | Lb/gal          | Ft          | Ft           |

Describe grouting procedure

Pumped down w / pressure grout

## SCREEN:

☐ Perforated pipe ☒ Manufactured
Diameter 16 Inches Length 60 FeetMaterial PVCSlot Size 0.85 Set From 118 Feet to 178 Feet

Other information

## WAS A PACKER OR SEAL USED?

☐ Yes ☒ No

If so, what material?

Describe packer(s) and location

## DISINFECTION: Was well disinfected upon completion?

☒ Yes, How? Chlorine
☐ No, Why Not?

Lab to which water quality sample sent for analysis

Well Owner: Carly Stapleman

Business Name:

Address: 724 E Shadow CreekCity, State, Zip: Sioux Falls SD 57108

## WELL LOG:

| FORMATION                | DEPTH      |            |
|--------------------------|------------|------------|
|                          | FROM       | TO         |
| <u>Brown top Soil</u>    | <u>0</u>   | <u>6</u>   |
| <u>Brown Clay</u>        | <u>6</u>   | <u>13</u>  |
| <u>Medium Brown Sand</u> | <u>13</u>  | <u>21</u>  |
| <u>Blue Clay</u>         | <u>21</u>  | <u>84</u>  |
| <u>Sandy Brown Clay</u>  | <u>84</u>  | <u>96</u>  |
| <u>Gray Clay / Sand</u>  | <u>96</u>  | <u>128</u> |
| <u>Gray clay</u>         | <u>128</u> | <u>135</u> |
| <u>Coarse Gravel</u>     | <u>135</u> | <u>80</u>  |
| <u>Rock</u>              | <u>180</u> |            |

## STATIC WATER LEVEL

98'

FEET

If flowing: closed in pressure

PSI

GPM flow

through

Inch pipe

Controlled by

☐ Valve☐ Reducers☐ Other

Reduced flow rate

GPM

Can well be completely shut in?

## WELL TEST DATA:

☐ Pumped Describe: Pumped w / turbine pump
☐ Bailed

☐ Other

Pumping Level Below Land Surface

110 Ft. After 2 Hrs. pumped 800 GPM

Ft. After Hrs. pumped GPM

If pump installed, pump rate: GPM

## REMARKS

RECEIVED

JUL 13 2023

OFFICE OF  
WATERThis well was drilled under license # 444 and this report is true and accurate.Drilling firm: Christensen Well & Irrigation

Signature of License Representative:

Carly Christensen

Signature of Well Owner or Equitable Property Holder:

Date: 7/7/23

# RECEIPT

## WATER RIGHTS PROGRAM South Dakota Department of Agriculture and Natural Resources

Date March 15, 2023

RECEIVED OF Bary/Debra Stapelman 724 E shadow Creek Ln., Sioux Falls SD 57108

The following amount in fees for services rendered as provided for by law:

|                                                                                                                        |                   |
|------------------------------------------------------------------------------------------------------------------------|-------------------|
| Fee for Application for Permit No. <u>8731-3</u> to Appropriate Water, to construct and to put water to beneficial use | \$ <u>850.00</u>  |
| Fee for Application for Permit No. _____ to Appropriate Water for Future use                                           | \$ _____          |
| Fee to retain Future Use Permit No. _____ after period of seven years.                                                 | \$ _____          |
| Fee for Inspecting Constructed Works, confirming beneficial use and issuing Water License No. <u>8731-3</u>            | \$ <u>200.00</u>  |
| Fee for Filing Transfer Form _____                                                                                     | \$ _____          |
| Fee for _____                                                                                                          | \$ _____          |
| Fee for Issuing New Well Driller's License No. _____                                                                   | \$ _____          |
| Fee for Renewal of Well Driller's License No. _____                                                                    | \$ _____          |
| Fee for Issuing Well Pump Installer's License No. _____                                                                | \$ _____          |
| Fee for Renewal of Well Pump Installer's License No. _____                                                             | \$ _____          |
| (Any Other Work Provided by Law) TOTAL                                                                                 | \$ <u>1050.00</u> |

By Eric Gronlund  
Chief Engineer  
Em



**DEPARTMENT of AGRICULTURE  
and NATURAL RESOURCES**

JOE FOSS BUILDING  
523 E. CAPITOL AVE  
PIERRE SD 57501-3182  
danr.sd.gov

**RECOMMENDATION OF CHIEF ENGINEER FOR WATER PERMIT  
APPLICATION NO. 8731-3, Gary Stapelman**

Pursuant to SDCL 46-2A-2, the following is the recommendation of the Chief Engineer, Water Rights Program, Department of Agriculture and Natural Resources concerning Water Permit Application No. 8731-3, Gary Stapelman, 724 E Shadow Creek Lane, Sioux Falls SD 57108.

The Chief Engineer is recommending APPROVAL of Application No. 8731-3 because 1) there is reasonable probability that there is unappropriated water available for the applicant's proposed use, 2) the proposed diversion can be developed without unlawful impairment of existing domestic water uses and water rights, 3) the proposed use is a beneficial use and 4) it is in the public interest as it pertains to matters of public interest within the regulatory authority of the Water Management Board with the following qualifications:

1. The well approved under Water Permit No. 8731-3 is located near domestic wells and other wells which may obtain water from the same aquifer. Water withdrawals shall be controlled so there is not a reduction of needed water supplies in adequate domestic wells or in adequate wells having prior water rights.
2. The well authorized by Permit No. 8731-3 shall be constructed by a licensed well driller and construction of the well and installation of the pump shall comply with Water Management Board Well Construction Rules, Chapter 74:02:04 with the well casing pressure grouted (bottom to top) pursuant to Section 74:02:04:28.
3. This Permit is approved subject to the irrigation water use questionnaire being submitted each year.

See report on application for additional information.

Eric Gronlund, Chief Engineer  
May 12, 2023

Report to the Chief Engineer  
On Water Permit Application No. 8731-3

Gary Stapelman

May 5th, 2023

Water Permit Application No. 8731-3 proposes to appropriate 1.67 cubic feet of water per second (cfs) from one well to be completed into the Lower Vermillion Missouri aquifer (approximately 200 feet deep) located in the approximate center of SW ¼ Section 3 for irrigation of 162 acres located in the SW ¼ Section 3; all in T93N-R51W. The site of interest is located approximately 9 miles northeast of Vermillion, SD in Clay County.

**AQUIFER:** Lower Vermillion Missouri (LVM)


**HYDROGEOLOGY:**

The Lower Vermillion Missouri aquifer, referred to as the LVM aquifer for the remainder of this report, is a buried glacial outwash that was deposited by meltwater streams beyond the margin of active glacial ice (Stephens, 1967). The LVM aquifer materials range in size from a coarse sand to a coarse gravel (Niehus, 1994). The LVM aquifer is primarily confined but can be locally found under unconfined conditions in the flood plain of the Vermillion River (Niehus, 1994; Stephens, 1967). The LVM aquifer has an average thickness of approximately 100 feet in Clay County (Stephens, 1967). Table 1 shows the information related to the areal extent of the LVM aquifer, the area utilized for this report is approximately 106,000 acres (Mathiowetz, 2018).

**Table 1.** Estimated areal extent for the historic LVM aquifer boundary (Hedges and others, 1982), the portion of the UVM:S aquifer that overlies the historic LVM aquifer boundary (Buhler, 2014). The current LVM aquifer boundary (Mathiowetz, 2018), and the unconfined portion of the LVM aquifer along the Vermillion River (modified from Jensen, 2000; modified from Stonesifer, 2013).

| <b>Delineation</b>                                                                                                                                                      | <b>Estimated Areal Extent (acres)</b> |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------|
| <b>Historic Lower Vermillion Missouri Aquifer</b> (modified from Hedges and others, 1982)                                                                               | 124,000                               |
| <b>Upper Vermillion Missouri: South Aquifer (UVM:S)</b> (modified from Buhler, 2014) - Portion that overlies LVM aquifer boundary estimated by Hedges and others, 1982. | 18,000                                |
| <b>Current Lower Vermillion Missouri Aquifer*</b> (Mathiowetz, 2018)                                                                                                    | 106,000                               |
| <b>Unconfined Portion of Lower Vermillion Missouri Aquifer - not enclosed in UVM:S</b> (Buhler, 2014) (modified from Jensen, 2000; modified from Stonesifer, 2013)      | 12,000                                |
| *Estimated by subtracting UVM:S aquifer boundary (Buhler, 2014) from historic boundary (Hedges and others, 1982)                                                        |                                       |

The LVM aquifer is hydrologically connected to the Upper Vermillion Missouri: South (UVM:S) aquifer to the north, the Missouri: Elk Point aquifer to the south, the underlying Dakota aquifer, and the Vermillion River (Buhler, 2014; Mathiowetz, 2018; Niehus, 1994; Stephens, 1967). Hedges and others (1982) delineated a boundary between the Upper Vermillion Missouri aquifer and LVM aquifer with portions of each boundary being modified by Buhler (2014) and Mathiowetz (2018) in response to additional study of the Upper Vermillion Missouri aquifer, as shown on Figure 1.



**Figure 1.** Map of the approximate LVM aquifer boundary delineated by Hedges and others (1982) with a portion of the UVM:S and LVM aquifer boundary estimated by Buhler (2014) and Mathiowetz (2018) respectively, and the location of proposed diversion point for Water Permit Application No. 8731-3, and LVM aquifer water rights/permits and observation wells (Water Rights, 2023b and 2023c). Note a number of water rights/permits considered to be appropriating water from the Upper Vermillion Missouri: South for the purposes of water management have not been formally reassigned so they still show up in Water Rights' databases (and therefore this map) as LVM permits.

A water well completion report was not submitted with the application. The nearest water well completion report is located 0.4 miles north of the diversion point of this application and was completed into the LVM aquifer on January 17<sup>th</sup>, 2013 (Water Rights, 2023b). The water well completion report has a saturated aquifer thickness of at least 112 feet. The depth to the top of aquifer material is 88 feet below the ground surface, and static water level is also at 88 feet below the ground surface at the day of completion (SDGS, 2023; Water Rights, 2023b). Based

on water well completion reports near the proposed diversion point and this water well completion report, the LVM aquifer is expected to be confined at the diversion point (SDGS, 2023; Water Rights, 2023b and 2023d).

### **South Dakota Codified Law (SDCL) 46-2A-9**

Pursuant to SDCL 46-2A-9, “A permit to appropriate water may be issued only if there is a reasonable probability that unappropriated water is available for the applicant’s proposed use, the proposed diversion can be developed without unlawful impairment of existing domestic water uses and water rights, the proposed use is a beneficial use, and the permit is in the public interest as it pertains to matters of public interest within the regulatory authority of the Water Management Board as defined by §§ 46-2-9 and 46-2-11.” This report will address the availability of unappropriated water and the potential for unlawful impairment of existing domestic uses and water rights within the LVM aquifer.

### **WATER AVAILABILITY:**

Water Permit Application No. 8731-3 proposes to appropriate water from the LVM aquifer. The probability of unappropriated water being available from the aquifer can be evaluated by considering SDCL 46-6-3.1, which requires “No application to appropriate groundwater may be approved if, according to the best information reasonably available, it is probable that the quantity of water withdrawn annually from a groundwater source will exceed the quantity of the average estimated annual recharge of water to the groundwater source. An application may be approved, however, for withdrawals of groundwater from any groundwater formation older than or stratigraphically lower than the greenhorn formation in excess of the average estimated annual recharge for use by water distribution systems.” The LVM aquifer is not older than or stratigraphically lower than the Greenhorn Formation, and the applicant’s proposed use is not for use in a water distribution system as defined by SDCL 46-1-6(17). Therefore, the average annual recharge and average annual withdrawal rates to and from the LVM aquifer must be considered.

### **HYDROLOGIC BUDGET:**

#### **Recharge**

Recharge to the LVM aquifer is received primarily through infiltration of precipitation where the aquifer is at or near land surface, groundwater inflow from the Upper Vermillion Missouri: South aquifer, seepage from Vermillion River, and leakage from the underlying Dakota aquifer (Niehus, 1994; Stephens, 1967). Using observation well analysis, Hedges and others (1985) estimated a recharge rate of 3.8 inches per year for the unconfined portion of the LVM aquifer. However, Stonesifer (2013) recalculated the recharge rate to be an estimated 4.58 inches per year by using the same method but with additional observation well data. The unconfined area for this primarily confined aquifer is approximately 12,000 acres (Table 1; modified from Jensen, 2000; modified from Stonesifer, 2013). Therefore, the estimated average annual recharge rate for the unconfined portion of the LVM aquifer is approximately 4,580 acre-feet/year (based on Stonesifer, 2013 and modified from Jensen, 2000).

It is assumed that the confined portion of the LVM aquifer recharges at a similar rate and is hydrologically similar to the confined portion of the Upper Vermillion Missouri aquifer. Using regional flow-net analysis, Hedges and others (1985) estimated the recharge rate of the, primarily confined, Upper Vermillion Missouri aquifer to be approximately 0.25 inches per year. The confined portion of the LVM aquifer is approximately 94,000 acres, this was found by subtracting the unconfined area from the current total area on Table 1. Using the Hedges and others (1985) confined recharge rate multiplied by the confined portion areal extent, the average annual recharge rate for the confined portion of the LVM aquifer is approximately 1,960 acre-feet per year. Combining average annual recharge rate for both the confined and unconfined portions of the LVM aquifer (within the LVM aquifer within Hedges and others (1982) historical aquifer boundary minus Buhler (2014) delineation of the UVM:S aquifer boundary), the average annual recharge rate is approximately 6,540 acre-feet per year.

## **Discharge**

Discharge from the LVM aquifer in South Dakota primarily occurs through well withdrawals, seepage to surface water features, and evapotranspiration in areas where the aquifer is at or near land surface. There are 96 water rights/permits authorized to appropriate water from the LVM aquifer within the historical aquifer boundary delineated by Hedges and others (1982) (Water Rights, 2023c). However, 61 water rights/permits are in both the LVM aquifer boundary delineated by Hedges and others (1982) and the Upper Vermillion Missouri: South aquifer boundary delineated by Buhler (2014). Of the 61 water rights/permits, 29 are currently withdrawing water from the Upper Vermillion Missouri: South aquifer and are still labeled as withdrawing water from the LVM aquifer. Therefore, by excluding the 29 water rights/permits that are withdrawing from the Upper Vermillion Missouri: South aquifer from the 96 water rights/permits, there are 67 water rights/permits authorized to appropriate water from the LVM aquifer within the current aquifer boundary delineated by Mathiowetz (2018). There are no future use permits reserving water from the LVM aquifer (Water Rights, 2023c).

Table 2 summarizes the 7 non-irrigation water rights/permits authorized to appropriate water from the LVM aquifer with the estimated annual use for each water right/permit as determined by their limiting diversion rate or annual volume. The data on Table 2 is broken up into two sets of water rights/permits 1) those that are located in the historic aquifer boundary by Hedges and others (1982) but not in the Upper Vermillion Missouri: South aquifer boundary delineated by Buhler (2014) and 2) water rights/permits that are located within both boundaries. The amount of water withdrawn was estimated by assuming the non-irrigation water rights/permits limited by an annual volume will withdraw their entire appropriated volume every year. It is estimated that the non-irrigation water rights/permits limited only by a diversion rate will pump at their maximum permitted diversion rate for 60 percent of the time. This is a standard method used by the DANR-Water Rights Program for estimating average annual withdrawals by non-irrigation appropriations limited solely by diversion rate. It is likely an overestimate of water withdrawn by water rights/permits only limited by diversion rate. Overall, the estimated average annual withdrawal rate for the LVM aquifer non-irrigation water rights/permits within the historic aquifer boundary (Hedges and others, 1982) is approximately 1,224.4 acre-feet/year, and

approximately 48.6 acre-feet/year excluding water rights/permits that are in the Upper Vermillion Missouri: South delineation by Buhler (2014) (Table 2) (Water Rights, 2023c).

**Table 2.** Estimated average annual use for non-irrigation water rights/permits authorized to appropriate water from the LVM aquifer within the historic aquifer boundary by Hedges and others (1982) but not the UVM:S aquifer delineation by Buhler (2014), and non-irrigation water rights within aquifer boundary delineated by Hedges and others (1982) and Buhler's (2014) UVM:S boundary (Water Rights, 2023c).

| Permit No.                                                                                          | Name                        | Uses | Status | Authorized Diversion Rate (cfs) | Authorized Annual Volume (acre-feet) | Estimated Use (acre-feet/year) |
|-----------------------------------------------------------------------------------------------------|-----------------------------|------|--------|---------------------------------|--------------------------------------|--------------------------------|
| 1870-3                                                                                              | USD FACILITIES MGMT         | INS  | LC     | 0.03                            | NA                                   | 13.0                           |
| 6397-3                                                                                              | SD DEPT OF TRANSPORTATION   | INS  | LC     | 0.033                           | NA                                   | 14.3                           |
| 8222-3                                                                                              | SOUTHEAST FARMERS COOP      | COM  | PE     | 0.167                           | 18.4                                 | 18.4                           |
| 8257-3                                                                                              | THEIN WELL CO INC           | COM  | PE     | 0.089                           | 1                                    | 1                              |
| 8479-3                                                                                              | KNIFE RIVER                 | IND  | PE     | 0.133                           | 1.84                                 | 1.84                           |
|                                                                                                     |                             |      |        |                                 | <b>Total:</b>                        | <b>48.6</b>                    |
| 3905-3*                                                                                             | CLAY RURAL WATER SYSTEM INC | RWS  | LC     | 2                               | NA                                   | 868.8                          |
| 5979-3*                                                                                             | CLAY RURAL WATER SYSTEM INC | RWS  | LC     | 2                               | 307                                  | 307                            |
|                                                                                                     |                             |      |        |                                 | <b>Total:</b>                        | <b>1175.8</b>                  |
| *Within aquifer boundary delineated by Hedges and others (1982) and Buhler's (2014) UVM:S boundary  |                             |      |        |                                 |                                      |                                |
| LC Licensed Water Right, PE Water Permit, INS Institutional, COM Commercial, RWS Rural Water System |                             |      |        |                                 |                                      |                                |

There are 89 irrigation water rights/permits appropriating water from the LVM aquifer within Hedges and others (1982) historical aquifer boundary (Water Rights, 2023c). Irrigation water rights/permits have been typically required to report their annual usage on an irrigation questionnaire since 1979. However, due to changes in farming practices, new equipment, and an increase in the number of permits from 43 in 2006 to 71 in 2013, the average over the entire period of record may not be an accurate reflection of average annual irrigation withdrawal at the present time. The average annual withdrawal rate for the LVM aquifer within Hedges and others (1982) historical boundary for irrigation water rights/permits that have reported over the past ten years of record (2012 to 2021) is approximately 3,015 acre-feet per year (Table 3) (Water Rights, 2023a).

There are 60 irrigation water rights/permits appropriating water from the LVM aquifer within Hedges and others (1982) historical aquifer boundary excluding rights/permits within delineation UVM:S aquifer by Buhler (2014) (Water Rights, 2023c). However, due to changes in farming practices and an increase in the number of permits from 27 in 2006 to 45 in 2013, the average over the entire period of record may not be an accurate reflection of actual average annual withdrawal at the present time. The average annual withdrawal rate for the LVM aquifer irrigation water rights/permits that have reported over the past ten years of record (2012 to 2021) is approximately 1,866 acre-feet per year (Table 3) (Water Rights, 2023a).

Application No. 8731-3 is requesting to irrigate 162 acres (Water Rights, 2023c). Generally, irrigators in eastern South Dakota apply less than one foot of water per acre per year. However, to account for fluctuation in wet and dry cycles from year to year, the one foot of water per acre per year application rate will be used to somewhat overestimate the average annual withdrawal rate for this irrigation water permit application. Therefore, the estimated average annual withdrawal rate for Application No. 8731-3 is approximately 162 acre-feet per year.

There are eight water permits approved in 2022 and early 2023 (Nos. 8632-3, 8589-3, 8641-3, 8672-3, 8680-3, 8692-3, 8693-3, and 8711-3) and two other pending applications in 2023 (Nos. 8725-3 and 8726-3) that were not included in the irrigation questionnaire compilation and need to be accounted for. The new permits are authorized to irrigate 872 acres, while the pending applications, including this application (No. 8731-3), propose to irrigate 383 acres. All together a total of 1,255 acres are planned to be irrigated (Water Rights, 2023c). Assuming one foot of water per acre per year, the withdrawal rate for these water permits/applications is approximately 1,255 acre-feet per year. The average annual withdrawal rate for irrigation appropriations from 2012 to 2021 combined with 2022 and 2023 permits and new applications, including this one, within Hedges and others (1982) historical aquifer boundary, is approximately 4,270 acre-feet per year (Table 3) (Water Rights, 2023a). The average annual withdrawal rate for irrigation appropriations from 2012 to 2021 combined with 2022 and 2023 permits and new applications, including this one, within Hedges and others (1982) historical aquifer boundary excluding water rights/permits within delineation UVM:S aquifer by Buhler (2014), is approximately 3,121 acre-feet per year (Table 3) (Water Rights, 2023a).

There are domestic wells completed into the LVM aquifer that do not require a water right/permit, so the withdrawal amount from those wells is unknown (Water Rights, 2023d). Due to their relatively low diversion rates, withdrawals from domestic wells are not considered to be a significant portion of the hydrologic budget. Additionally, with the development of rural water systems in areas where the LVM aquifer is the uppermost aquifer available; it is likely some domestic users may have transitioned to rural water. Therefore, the quantity of water withdrawn by domestic wells is estimated to be negligible to the hydrologic budget for the LVM aquifer.

**Table 3.** Reported irrigation uses from the LVM aquifer for water right/permits within the historical boundary of LVM aquifer excluding delineation UVM:S aquifer (Buhler, 2014) (Water Rights, 2023a)

| Historical Boundary of LVM aquifer (Hedges and others, 1982) |                          |                           | Historical Boundary of LVM aquifer (Hedges and others, 1982), Excluding UVM:S Aquifer Boundary (Buhler, 2014) |                          |                           |
|--------------------------------------------------------------|--------------------------|---------------------------|---------------------------------------------------------------------------------------------------------------|--------------------------|---------------------------|
| Year                                                         | Number of Permit/License | Annual Pumpage (ac-ft/yr) | Year                                                                                                          | Number of Permit/License | Annual Pumpage (ac-ft/yr) |
| 1979                                                         | 49                       | 1163.0                    | 1979                                                                                                          | 40                       | 810.5                     |
| 1980                                                         | 47                       | 2417.0                    | 1980                                                                                                          | 38                       | 1995.0                    |
| 1981                                                         | 49                       | 1543.0                    | 1981                                                                                                          | 39                       | 1205.4                    |
| 1982                                                         | 37                       | 870.0                     | 1982                                                                                                          | 27                       | 758.3                     |
| 1983                                                         | 38                       | 716.3                     | 1983                                                                                                          | 28                       | 644.7                     |
| 1984                                                         | 47                       | 691.0                     | 1984                                                                                                          | 37                       | 549.0                     |
| 1985                                                         | 46                       | 1328.2                    | 1985                                                                                                          | 36                       | 927.2                     |
| 1986                                                         | 45                       | 1047.5                    | 1986                                                                                                          | 35                       | 807.5                     |
| 1987                                                         | 37                       | 1115.4                    | 1987                                                                                                          | 27                       | 794.4                     |
| 1988                                                         | 38                       | 2083.8                    | 1988                                                                                                          | 28                       | 1442.4                    |
| 1989                                                         | 38                       | 2301.2                    | 1989                                                                                                          | 28                       | 1522.2                    |
| 1990                                                         | 38                       | 2113.2                    | 1990                                                                                                          | 28                       | 1288.2                    |
| 1991                                                         | 39                       | 1670.1                    | 1991                                                                                                          | 29                       | 1044.1                    |
| 1992                                                         | 39                       | 168.8                     | 1992                                                                                                          | 29                       | 116.7                     |
| 1993                                                         | 39                       | 0.0                       | 1993                                                                                                          | 29                       | 0.0                       |
| 1994                                                         | 39                       | 517.3                     | 1994                                                                                                          | 29                       | 308.7                     |
| 1995                                                         | 37                       | 506.6                     | 1995                                                                                                          | 28                       | 368.2                     |
| 1996                                                         | 36                       | 997.6                     | 1996                                                                                                          | 27                       | 572.9                     |
| 1997                                                         | 36                       | 1085.0                    | 1997                                                                                                          | 27                       | 645.0                     |
| 1998                                                         | 36                       | 1032.9                    | 1998                                                                                                          | 26                       | 736.6                     |
| 1999                                                         | 38                       | 900.6                     | 1999                                                                                                          | 27                       | 698.9                     |
| 2000                                                         | 38                       | 2041.7                    | 2000                                                                                                          | 27                       | 1574.9                    |
| 2001                                                         | 38                       | 2037.0                    | 2001                                                                                                          | 27                       | 1781.8                    |
| 2002                                                         | 40                       | 1762.3                    | 2002                                                                                                          | 29                       | 1123.2                    |
| 2003                                                         | 40                       | 1800.6                    | 2003                                                                                                          | 29                       | 1470.6                    |
| 2004                                                         | 39                       | 1747.5                    | 2004                                                                                                          | 28                       | 1167.6                    |
| 2005                                                         | 45                       | 1410.2                    | 2005                                                                                                          | 28                       | 1071.1                    |
| 2006                                                         | 43                       | 2674.5                    | 2006                                                                                                          | 27                       | 1734.3                    |
| 2007                                                         | 50                       | 2909.1                    | 2007                                                                                                          | 26                       | 1327.0                    |
| 2008                                                         | 55                       | 4301.3                    | 2008                                                                                                          | 28                       | 911.9                     |
| 2009                                                         | 58                       | 482.6                     | 2009                                                                                                          | 30                       | 460.8                     |
| 2010                                                         | 59                       | 144.6                     | 2010                                                                                                          | 30                       | 134.0                     |
| 2011                                                         | 62                       | 2195.1                    | 2011                                                                                                          | 33                       | 1219.4                    |
| 2012                                                         | 61                       | 7759.5                    | 2012                                                                                                          | 33                       | 3355.3                    |
| 2013                                                         | 71                       | 4109.1                    | 2013                                                                                                          | 45                       | 2856.5                    |
| 2014                                                         | 75                       | 1576.3                    | 2014                                                                                                          | 48                       | 1006.4                    |
| 2015                                                         | 78                       | 1925.8                    | 2015                                                                                                          | 50                       | 1473.5                    |
| 2016                                                         | 79                       | 2187.5                    | 2016                                                                                                          | 51                       | 1779.0                    |
| 2017                                                         | 79                       | 3156.6                    | 2017                                                                                                          | 52                       | 2439.3                    |
| 2018                                                         | 79                       | 427.7                     | 2018                                                                                                          | 52                       | 419.4                     |
| 2019                                                         | 79                       | 339.6                     | 2019                                                                                                          | 52                       | 333.0                     |
| 2020                                                         | 78                       | 3353.2                    | 2020                                                                                                          | 51                       | 1972.5                    |
| 2021                                                         | 80                       | 5316.2                    | 2021                                                                                                          | 54                       | 3026.7                    |
| Average 1979-2021                                            |                          | 1812.2                    | Average 1979-2021                                                                                             |                          | 1159.9                    |
| Average 2012-2021                                            |                          | 3015.2                    | Average 2012-2021                                                                                             |                          | 1866.2                    |

## Hydrologic Budget Summary

The average annual recharge rate for the unconfined portion LVM aquifer not enclosed in the UVM:S aquifer (Buhler, 2014) is approximately 4,580 acre-feet/year. The average annual recharge rate for the current confined portion LVM aquifer (Mathiowetz, 2018) is approximately 1,960 acre-feet/year. Combining average annual recharge rate both the current confined and unconfined portions of the LVM aquifer not enclosed in the UVM:S aquifer, the average annual recharge rate is approximately 6,540 acre-feet per year.

The average annual withdrawal rate from the LVM aquifer within Hedges and others (1982) historical aquifer boundary (the non-irrigation appropriations (1,224 acre-feet/year); the average annual withdrawal rate for irrigation appropriations from 2012 to 2021, 2022-2023 water permits, and new applications, including this one, (4,270 acre-feet/year)) is approximately 5,494 acre-feet per year, also shown on Table 4 (Water Rights, 2023a).

The average annual withdrawal rate from the LVM aquifer within Hedges and others (1982) historical aquifer boundary excluding rights/permits within delineation UVM:S aquifer by Buhler (2014) (the non-irrigation appropriations (49 acre-feet/year); the average annual withdrawal rate for irrigation appropriations from 2012 to 2021, 2022-2023 water permits, and new applications, including this one, (3,121 acre-feet/year)) is approximately 3,170 acre-feet per year, also shown on Table 4 (Water Rights, 2023a).

Collectively, the average annual recharge rate for both the confined and unconfined portions of the LVM aquifer is greater than the average annual withdrawal rate from both the LVM aquifer within Hedges and others (1982) historical aquifer boundary and the LVM aquifer within Buhler (2014) and Mathiowetz (2018) boundary delineated portions of the UVM:S and LVM aquifers. Based on the hydrologic budget, there is a reasonable probability unappropriated water is available from the LVM aquifer for the proposed appropriation.


**Table 4.** List of water rights/permits withdrawals and new applications (if approved) approximate withdrawals from both the historic boundary of the LVM and current boundary of the LVM excluding the UVM:S delineated areas made by Buhler (2014) (Water Rights, 2023a)

|                                      | <b>Historical Boundary of the LVM Aquifer (Hedges and others, 1982) Pumpage (ac-ft/yr)</b> | <b>Historic Boundary of the LVM Aquifer (Hedges and others, 1982), Excluding UVM:S Aquifer Boundary (Buhler 2014) Pumpage (ac-ft/yr)</b> |
|--------------------------------------|--------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------|
| Non-Irrigation Appropriation         | 1,224                                                                                      | 49                                                                                                                                       |
| Irrigation Appropriation (2012-2022) | 3,015                                                                                      | 1,866                                                                                                                                    |
| New Permits (2022-2023)              | 872                                                                                        | 872                                                                                                                                      |
| New Applications                     | 383                                                                                        | 383                                                                                                                                      |
| <b>Total</b>                         | <b>5,494</b>                                                                               | <b>3,170</b>                                                                                                                             |


## OBSERVATION WELL DATA:

Administrative Rule of South Dakota (ARSD) 74:02:05:07 requires that the Water Management Board shall rely upon the record of observation well measurements in addition to other data to determine that the quantity of water withdrawn annually from the aquifer does not exceed the estimated average annual recharge of the aquifer.


The DANR-Water Rights Program monitors ten observation wells completed into the LVM aquifer with two additional observation wells (CL-80J and CL-66AR) that are within both the historic aquifer boundary delineated by Hedges and others (1982) and Upper Vermillion Missouri: South aquifer boundary as defined by Buhler (2014), with observation wells in the area of this application shown on Figure 5 (Water Rights, 2023b). These observation wells provide data on how the aquifer reacts to regional climatic conditions and local pumping. The three closest observation wells to the diversion point are CL-80H (approximately 1.6 miles northwest), CL-80F (approximately 3.3 miles southwest), and CL-80IR (approximately 5.7 miles northwest) (Water Rights, 2023b). The hydrographs for these observation wells are displayed in Figures 2, 3, and 4 respectively (Water Rights, 2023b). The data points utilized to construct the hydrographs are measurements of the static water level in the observation wells from the top of the well casing. It is worth noting the hydrograph titles display DENR Water Rights Observation Well on the hydrographs when the titles should display DANR Water Rights Observation Well on hydrographs.



**Figure 2.** Hydrograph for observation well CL-80H (Water Rights, 2023b)



**Figure 3.** Hydrograph for observation well CL-80F (Water Rights, 2023b)




**Figure 4.** Hydrograph for observation well CL-80IR (Water Rights, 2023b)

A majority of the observation wells in the LVM aquifer have a stable trend in the water level. The data shown on Figures 2, 3, and 4 share a similar trend with most of the other observation wells in the LVM aquifer. The hydrographs for the LVM aquifer observation wells indicate that the aquifer responds well to climatic conditions because water levels are rising during wetter periods (early spring snowmelt and precipitation) and declining to a stable water level during drier periods. Additionally, the water levels in the observation wells display that the amount of recharge to and natural discharge from the aquifer greatly exceeds pumping with the aquifer water levels returning to pre-pumping conditions between irrigation seasons. Aquifer recovery

indicates that climatic conditions and therefore, the effects of recharge to and natural discharges from the aquifer govern the long-term fluctuations of waters levels in the aquifer rather than the impacts of pumping from the LVM aquifer. By recognizing that both recharge to and natural discharge from an aquifer can be captured for pumping, the observation well hydrographs demonstrate unappropriated water is available for the proposed appropriation.

#### **POTENTIAL FOR UNLAWFUL IMPAIRMENT OF EXISTING WATER RIGHTS:**

Currently, 67 water rights/permits are authorized to appropriate water from the LVM aquifer, partially shown on Figure 5, within the historic boundary of the aquifer mapped by Hedges and others (1982) excluding the area of the UVM:S as delineated by Buhler (2014) (Water Rights, 2023c). Table 5 lists nearby water rights/permits that are shown on Figure 5. The closest water right/permit to the diversion point for this application is Water Right No. 7504-3 which is held by Steven Andrews. The diversion point for Water Right No. 7504-3 is located approximately 0.5 miles north of the proposed diversion point for this application (Water Rights, 2023c). There are domestic wells on file with the DANR-Water Rights Program that are completed into the LVM aquifer, with the closest domestic well on file (not held by the applicant) approximately 0.4 miles north of the diversion point based on the legal description provided by the well driller on the well completion report (Water Rights, 2023d). There could potentially be other domestic wells completed into the LVM aquifer near the diversion point that are not on file with the DANR-Water Rights Program.



**Figure 5.** Map of the proposed diversion point for Water Permit Application No. 8731-3 and nearby LVM aquifer water rights/permits and observation wells (Water Rights, 2023b and 2023c).

**Table 5.** List of water rights/permits shown in Figure 5 (Water Rights, 2023c).

| Permit | Name/Business            | Priority   | Status  | Use Type   | CFS   | Acres  |
|--------|--------------------------|------------|---------|------------|-------|--------|
| 2966-3 | Harold/Beverly Fischer   | 08/25/1976 | License | Irrigation | 1.05  | 74     |
| 3039-3 | Ronald Alfred Johnson    | 09/01/1976 | License | Irrigation | 2     | 140    |
| 4664-3 | William O'Connor         | 03/05/1981 | License | Irrigation | 1.7   | 120    |
| 6303-3 | Thelma R & Ronald Lind   | 01/31/2002 | License | Irrigation | 1.78  | 132    |
| 6951-3 | Verlyn Hybertson         | 01/22/2008 | License | Irrigation | 1.78  | 132    |
| 7217-3 | Thelma R & Ronald Lind   | 10/28/2010 | License | Irrigation | 3.34  | 202    |
| 7233-3 | Jerry Lange              | 02/28/2011 | Permit  | Irrigation | 1.56  | 136    |
| 7472-3 | Paul Bremer              | 10/22/2012 | License | Irrigation | 1.78  | 134    |
| 7477-3 | Chad Heckathorn          | 10/22/2012 | License | Irrigation | 1.78  | 115    |
| 7487-3 | Bottolfson Brothers      | 10/29/2012 | License | Irrigation | 1.56  | 140    |
| 7504-3 | Stevens Andrews          | 11/05/2012 | Permit  | Irrigation | 1.78  | 160    |
| 7562-3 | John T Lindstrom         | 12/14/2012 | License | Irrigation | 1.33  | 63     |
| 7631-3 | Gregoire Farms           | 01/14/2013 | License | Irrigation | 1.61  | 100    |
| 7632-3 | Gregoire Farms           | 01/14/2013 | Permit  | Irrigation | 4.44  | 250    |
| 7636-3 | Verlyn Jelsma            | 01/07/2013 | License | Irrigation | 0.58  | 69     |
| 7642-3 | Tom Austin               | 01/16/2013 | License | Irrigation | 1.22  | 63     |
| 7679-3 | Scott Heritage Farms LLP | 02/04/2013 | Permit  | Irrigation | 1.67  | 124.6  |
| 7836-3 | Craig Nelson             | 04/25/2013 | License | Irrigation | 1.78  | 145    |
| 8257-3 | Thein Well Co Inc        | 12/27/2016 | Permit  | Commercial | 0.089 | 0      |
| 8632-3 | Bottolfson Brothers      | 02/03/2022 | Permit  | Irrigation | 1.78  | 122.04 |

The LVM aquifer is primarily under confined conditions, but it can be found to be locally unconfined near the Vermillion River. Based on well completion reports near the proposed diversion point for this application, it is expected to be under confined conditions. In a confined aquifer, drawdown from a pumping well can extend some distance from the well. The Water Management Board recognizes that putting water to beneficial use requires a certain amount of drawdown to occur. The Board has developed rules to allow water to be placed to maximum beneficial use without the necessity of maintaining artesian head pressure for domestic use. The Water Management Board defined an “adversely impacted domestic well” in ARSD 74:02:04:20(7) as:

“A well in which the pump intake was set at least 20 feet below the top of the aquifer at the time of construction or, if the aquifer is less than 20 feet thick, is as near to the bottom of the aquifer as is practical and the water level of the aquifer has declined to a level that the pump will no longer deliver sufficient water for the well owner’s needs.”

The Water Management Board considered the delivery of water by artesian head pressure versus maximum beneficial use during the issuance of Water Right No. 2313-2 for Coca-Cola Bottling Company of the Black Hills. The Water Management Board adopted the Findings of Facts and Conclusions of Law that noted the reservation of artesian head pressure for delivery of water would be inconsistent with SDCL 46-1-4 which states, “general welfare requires that the water resources of the state be put to beneficial use to the fullest extent of which they are capable...” (Water Rights, 1995). Furthermore, the Water Management Board found if increased cost or decreased production as a result of impacts on artesian head pressure by legitimate users is to be considered as an unlawful impairment, it would also conflict with SDCL 46-1-4 (Water Rights, 1995). With that in mind, some existing well owners may need to install or lower pumps depending on the specific characteristics of the LVM aquifer at their location. However, when considering the statutes (SDCL 46-1-4 and 46-6-6.1), rules (ARSD 74:02:04:20(6) and (7)), history of irrigation in the area without any recent complaints of well interference (Water Rights, 2023e), the saturated aquifer thickness near the diversion point, any drawdown created from the diversion is not expected to cause an unlawful impairment on existing water right/permit holders or domestic users with adequate wells. Therefore, there is a reasonable probability that any interference from the proposed appropriation will not impose unlawful impairments on existing users with adequate wells.

## **CONCLUSIONS:**


1. Water Permit Application No. 8731-3 proposes to appropriate 1.67 cfs of water for irrigation of 162 acres from one proposed well to be completed into the LVM aquifer. The site of interest is located approximately 9 miles northeast of Vermillion, SD.
2. Based on observation well data and the hydrologic budget, there is a reasonable probability that unappropriated water is available from the LVM aquifer to supply the proposed appropriation.

3. There is a reasonable probability that the diversion by Water Permit Application No. 8731-3 will not unlawfully impair adequate wells for existing water rights/permits and domestic uses.



Tyler Jensen  
Natural Resources Engineer I  
SD DANR - Water Rights Program

Reviewed by:



for Adam Mathiowetz, PE  
Natural Resources Engineer IV  
SD DANR - Water Rights Program

### References

- Buhler, K. A. 2014. Report to the Chief Engineer on 21 Water Permit Applications from the Upper Vermillion Missouri Aquifer. SD DANR – Water Rights Program, Joe Foss Bldg. Pierre, SD.
- Hedges, L.S., Allen, J., Holly, D.E., 1985. Evaluation of Ground-Water Resources Eastern South Dakota and Upper Big Sioux River, South Dakota and Iowa, Task 7: Ground Water Recharge; United States Army Corps of Engineers Contract DACW 45-80-C-0185.
- Hedges, L.S., Burch, S.L., Iles, D.L., Barari, R.A., and Schoon, R.A. 1982. Evaluation of Ground-Water Resources Eastern South Dakota and Upper Big Sioux River, South Dakota and Iowa, Task 1: Bed rock Topography and Distribution, Task 2: Extent of Aquifers, Task 3 Ground-Water Storage, Task 4: Computerized Data Base. United States Army Corps of Engineers Contract DACW 45-80-C-0185.
- Jensen, A.R., 2000. First Occurrence of Aquifer Materials in Clay County, South Dakota. SD DANR-Geological Survey Aquifer Materials Map 1. Vermillion, SD.
- Mathiowetz, A. 2018. Report to the Chief Engineer on Water Permit Application 8335-3. Natural Resource Engineer IV, SD DANR – Water Rights Program, Joe Foss Bldg. Pierre, SD.
- Niehus, C.A., 1994. Water Resources of Lincoln and Union Counties, South Dakota. U.S. Geological Survey Water-Resources Investigations Report 93-4195. U.S. Geological Survey. Rapid City, SD.

- SDGS, 2023. South Dakota Geological Survey Lithologic Logs Database. Accessed March 15, 2023. <http://cf.sddanr.net/lithdb/>.
- Steen, N. 2022. Report to the Chief Engineer on Water Permit Application 8641-3. SD DANR – Water Rights Program, Joe Foss Bldg. Pierre, SD.
- Stephens, J.C., 1967. Geology and Water Resources of Clay Counties, South Dakota Part II: Water Resources. Bulletin 19. SD DANR-Geological Survey, Vermillion, SD.
- Stonesifer, J. R. 2013. Report to the Chief Engineer on Water Permit Application 7918-3. SD DANR – Water Rights Program, Joe Foss Bldg. Pierre, SD.
- Water Rights, 1995. Findings of Fact, Conclusions of Law, and Final Decision in the Matter of Water Permit Application No. 2313-2, Coca-Cola Bottling Company of the Black Hills. DANR-Water Rights Program file for Water Right No. 2313-2. Pierre, SD.
- Water Rights, 2023a. "1979-2021 Irrigation Summaries by Aquifer", SD DANR-Water Rights Program, Joe Foss Building, Pierre, SD.
- Water Rights, 2023b. Observation Well Data, SD DANR-Water Rights Program, Joe Foss Bldg, Pierre, SD.
- Water Rights, 2023c. Water Right/Permit Files, SD DANR-Water Rights Program, Joe Foss Bldg, Pierre, SD.
- Water Rights, 2023d. Well Completion Reports, SD DANR-Water Rights Program, Joe Foss Bldg, Pierre, SD.
- Water Rights, 2023e. County Files, SD DANR-Water Rights Program, Joe Foss Bldg, Pierre, SD.



**DEPARTMENT of AGRICULTURE  
and NATURAL RESOURCES**

JOE FOSS BUILDING  
523 E CAPITOL AVE  
PIERRE SD 57501-3182  
danr.sd.gov

**NOTE: TO BE SURE OF PUBLICATION ON  
THE CORRECT DATES, CONTACT  
THE NEWSPAPERS RIGHT AWAY.**

May 23, 2023

Gary Stapelman  
724 E Shadow Creek Ln  
Sioux Falls Sd 57108

Dear Mr. Stapelman:

Water Permit Application No. 8731-3 for irrigation use have been examined and found to comply with the South Dakota Water Laws and applicable rules. A notice has been sent to the Plain Talk printed at Vermillion SD (Ph # 605 624-2695) and the Daily Press & Dakotan printed at Yankton SD (Ph # 605 665-7811). You will need to contact the newspapers and authorize publication of this notice. For your information, a copy of the notice, the recommendation of the Chief Engineer and report on the application are enclosed. Please review the notice prior to publication and notify this office, if you have any corrections or questions.

Be sure to contact the above newspapers to authorize publication of your Notice and to arrange for payment. Early contact with the papers can eliminate delays. Upon receiving authorization from you, the publishers have been instructed to publish your notice. The newspapers have also been instructed to send us the Proof of Publication. We must receive Proof of Publication before action can be taken on the application.

Sincerely,

*Rachel Rodriguez*

Rachel Rodriguez  
Water Rights Program  
(605) 773-3352

enclosures

NOTE: If you plan to contest any part of the Chief Engineer's recommendation, you must file a petition pursuant to the procedures outlined in the attached notice of hearing. The Water Management Board will then consider your concerns during a hearing on the application.

Instruction to Newspaper - Publish the Notice on June 2, 2023. The applicant is responsible for payment.

---

NOTICE OF APPLICATION NO. 8731-3 to Appropriate Water

Notice is given that Gary Stapelman, 724 E Shadow Creek Ln, Sioux Falls SD 57108 has filed an application for a water permit to appropriate 1.67 cubic feet of water per second (cfs) from one well to be completed into the Lower Vermillion Missouri Aquifer (approximately 200 feet deep) located in the approximate center of SW 1/4 Section 3 for irrigation of 162 acres located in the SW 1/4 Section 3; all in T93N-R51W. This site is located approximately 9 miles northeast of Vermillion SD.

Pursuant to SDCL 46-2A-2, the Chief Engineer recommends APPROVAL of Application No. 8731-3 with qualifications because 1) unappropriated water is available, 2) existing domestic water uses and water rights will not be unlawfully impaired, 3) it is a beneficial use of water, and 4) it is in the public interest as it pertains to matters within the regulatory authority of the Water Management Board. The Chief Engineer's recommendation with qualifications, the application, and staff report are available at <https://danr.sd.gov/public> or contact Ron Duvall for this information, or other information, at the Water Rights Program address provided below.

Any person interested in opposing this application or recommendation shall allege that the application, upon approval, will cause injury to the person that is unique from any injury suffered by the public in general. The injury must concern a matter either within the regulatory authority found in SDCL 46-2A-9 for approval or denial of the application, or other matter concerning the application within the regulatory authority of the board to act upon as defined by SDCL 46-2-9 and 46-2-11, or both. Any person meeting the petitioner requirements and wishing to be a party of record in a contested case hearing shall file a written petition to oppose the application with BOTH the applicant and Chief Engineer. A petition opposing the application shall be filed on a form provided by the Chief Engineer. The petition form is available online at <https://danr.sd.gov/public> or by contacting the Chief Engineer. The Chief Engineer's address is "Water Rights Program, Foss Building, 523 E Capitol, Pierre SD 57501" or call (605) 773-3352. The applicant's mailing address is given above. If contesting the Chief Engineer's recommendation, the applicant shall also file a petition. A petition filed by either an interested person or the applicant must be filed by June 12, 2023.

The petition shall include a statement describing the unique injury upon approval of the application on the petitioner, the petitioner's reasons for opposing the application, and the name and mailing address of the petitioner or the petitioner's legal counsel, if legal counsel is obtained.

Any interested person may file a comment on the application with the Chief Engineer. The comment shall be filed on a form provided by the Chief Engineer and is available online at <https://danr.sd.gov/public> or by calling (605) 773-3352 or writing the Chief Engineer at the address provided above. Filing a comment does not make the commenter a party of record or a participant in any hearing that may be held. Any comment must be filed by June 12, 2023.

If the applicant does not contest the recommendation of the Chief Engineer and no petition to oppose the application is received, the Chief Engineer shall act on the application pursuant to the recommendation with no hearing held before the Water Management Board. If a petition opposing the application or contesting the recommendation is filed, then a hearing will be scheduled, and the Water Management Board will consider this application. Notice of the hearing will be given to the applicant and any person filing a petition.

Published once at the total approximate cost of\_\_

**Rodriguez, Rachel**

Plain Talk

**From:** Rodriguez, Rachel  
**Sent:** Tuesday, May 23, 2023 11:32 AM  
**To:** Kelly Kronaizl  
**Subject:** 8731-3 Gary Stapelman - Public Notice  
**Attachments:** 8731-3 public.short\_final.docx; FORM8.FRM.doc

Attached is a notice to be published on June 2, 2023.

Gary Stapelman, 724 E Shadow Creek Ln, Sioux Fall SD 57108, (402-709-7132) has been notified to contact you to authorize publication and arrange for payment.

Please send the affidavit or return the attached Proof of Publication form ASAP to the Water Rights Program, 523 E Capitol, Pierre SD 57501.

Let me know if you have questions. Please acknowledge receipt of this email.

Thank you,

Rachel Rodriguez  
DANR | Program Assistant  
Rachel.Rodriguez@state.sd.us



**Rodriguez, Rachel**

*Yankton Press  
Dakota*

**From:** Rodriguez, Rachel  
**Sent:** Tuesday, May 23, 2023 11:34 AM  
**To:** Michael Pietz  
**Subject:** 8731-3 Gary Stapelman - Public Notice  
**Attachments:** 8731-3 public.short\_final.docx; FORM8.FRM.doc

Attached is a notice to be published on June 2, 2023.

Gary Stapelman, 724 E Shadow Creek Ln, Sioux Fall SD 57108, (402-709-7132) has been notified to contact you to authorize publication and arrange for payment.

Please send the affidavit or return the attached Proof of Publication form ASAP to the Water Rights Program, 523 E Capitol, Pierre SD 57501.

Let me know if you have questions. Please acknowledge receipt of this email.

Thank you,

Rachel Rodriguez  
DANR | Program Assistant  
[Rachel.Rodriguez@state.sd.us](mailto:Rachel.Rodriguez@state.sd.us)



# AFFIDAVIT OF PUBLICATION

PLAIN TALK

GARY STAPELMAN  
724 E SHADOW CREEK LANE  
SIOUX FALLS SD 57108

STATE OF SOUTH DAKOTA  
COUNTY OF CLAY

BETH RYE, BEING FIRST DULY SWORN ON OATH DEPOSES  
AND SAYS THAT (S)HE IS THE ADVERTISING DIRECTOR OF YANKTON  
MEDIA INC, A CORPORATION, THE PRINTER AND THE PUBLISHER OF THE  
PLAIN TALK, A LEGAL WEEKLY NEWSPAPER PUBLISHED AND CIRCULATED  
IN THE CITY OF VERMILLION, SAID COUNTY AND STATE, AND ONE OF  
THE OFFICIAL NEWSPAPERS OF THE SAID COUNTY OF FACTS STATED IN  
THIS AFFIDAVIT; THAT THE ANNEXED  
NOTICE OF APPLICATION NO.


TAKEN FROM THE PAPER, IN WHICH IT WAS LAST PUBLISHED IN THE  
NEWSPAPER ON THE 2nd DAY OF June, 2023  
THAT THE FULL AMOUNT OF THE FEE CHARGED FOR THE PUBLICATION  
OF SAID NOTICE TO WIT \$40.00 ENSURES TO THE  
BENEFITS OF THE PUBLISHER OF SAID NEWSPAPER AND THAT NO  
AGREEMENT AND UNDERSTANDING FOR THE DIVISION THEREOF HAS  
BEEN MADE WITH ANY OTHER PERSON, AND THAT NO PART THEREOF  
HAS BEEN AGREED TO BE PAID TO ANY PERSON WHOMSOEVER.

PUBLISHED ON: 06/02/2023

FILED ON: 06/20/2023

  
SUBSCRIBED AND SWORN TO BEFORE ME THIS 20th DAY OF June, 2023

NOTARY PUBLIC, SOUTH DAKOTA  
MY COMMISSION EXPIRES 7/15/2028



RECEIVED

JUN 22 2023

OFFICE OF  
WATER

Ad text : NOTICE OF APPLICATION NO. 8731-3 to Appropriate Water

Notice is given that Gary Stapelman, 724 E Shadow Creek Ln, Sioux Falls SD 57108 has filed an application for a water permit to appropriate 1.67 cubic feet of water per second (cfs) from one well to be completed into the Lower Vermillion Missouri Aquifer (approximately 200 feet deep) located in the approximate center of SW 1/4 Section 3 for irrigation of 162 acres located in the SW 1/4 Section 3; all in T93N-R51W. This site is located approximately 9 miles northeast of Vermillion SD.

Pursuant to SDCL 46-2A-2, the Chief Engineer recommends APPROVAL of Application No. 8731-3 with qualifications because 1) unappropriated water is available, 2) existing domestic water uses and water rights will not be unlawfully impaired, 3) it is a beneficial use of water, and 4) it is in the public interest as it pertains to matters within the regulatory authority of the Water Management Board. The Chief Engineers recommendation with qualifications, the application, and staff report are available at <https://danr.sd.gov/public> or contact Ron Duvall for this information, or other information, at the Water Rights Program address provided below.

Any person interested in opposing this application or recommendation shall allege that the application, upon approval, will cause injury to the person that is unique from any injury suffered by the public in general. The injury must concern a matter either within the regulatory authority found in SDCL 46-2A-9 for approval or denial of the application, or other matter concerning the application within the regulatory authority of the board to act upon as defined by SDCL 46-2-9 and 46-2-11, or both. Any person meeting the petitioner requirements and wishing to be a party of record in a contested case hearing shall file a written petition to oppose the application with BOTH the applicant and Chief Engineer. A petition opposing the application shall be filed on a form provided by the Chief Engineer. The petition form is available online at <https://danr.sd.gov/public> or by contacting the Chief Engineer. The Chief Engineer's address is "Water Rights Program, Foss Building, 523 E Capitol, Pierre SD 57501" or call (605) 773-3352. The applicant's mailing address is given above. If contesting the Chief Engineer's recommendation, the applicant shall also file a petition. A petition filed by either an interested person or the applicant must be filed by June 12, 2023.

The petition shall include a statement describing the unique injury upon approval of the application on the petitioner, the petitioner's reasons for opposing the application, and the name and mailing address of the petitioner or the petitioner's legal counsel, if legal counsel is obtained.

Any interested person may file a comment on the application with the Chief Engineer. The comment shall be filed on a form provided by the Chief Engineer and is available online at <https://danr.sd.gov/public> or by calling (605) 773-3352 or writing the Chief Engineer at the address provided above. Filing a comment does not make the commenter a party of record or a participant in any hearing that may be held. Any comment must be filed by June 12, 2023.

If the applicant does not contest the recommendation of the Chief Engineer and no petition to oppose the application is received, the Chief Engineer shall act on the application pursuant to the recommendation with no hearing held before the Water Management Board. If a petition opposing the application or contesting the recommendation is filed, then a hearing will be scheduled, and the Water Management Board will consider this application. Notice of the hearing will be given to the applicant and any person filing a petition.

Published once at the total approximate cost of \$40.00 and can be viewed free of charge at [www.sdpublicnotices.com](http://www.sdpublicnotices.com)

Published June 2, 2023.

# AFFIDAVIT OF PUBLICATION

YANKTON DAILY PRESS AND DAKOTAN

RECEIVED

JUN 05 2023

OFFICE OF  
WATER

GARY STAPELMAN  
724 E SHADOW CREEK LN  
SIOUX FALLS SD 57108


STATE OF SOUTH DAKOTA  
COUNTY OF YANKTON

KELLY HERTZ, BEING FIRST DULY SWORN ON OATH DEPOSES  
AND SAYS THAT (S)HE IS THE MANAGING EDITOR OF YANKTON  
MEDIA INC, A CORPORATION, THE PRINTER AND THE PUBLISHER OF THE  
YANKTON DAILY PRESS AND DAKOTAN, A LEGAL DAILY NEWSPAPER  
PUBLISHED AND CIRCULATED IN THE CITY OF YANKTON, SAID COUNTY  
AND STATE, AND ONE OF THE OFFICIAL NEWSPAPERS OF THE SAID  
COUNTY OF FACTS STATED IN THIS AFFIDAVIT; THAT THE ANNEXED  
NOTICE OF APPLICATION NO.

TAKEN FROM THE PAPER, IN WHICH IT WAS LAST PUBLISHED IN THE  
NEWSPAPER ON THE 2nd DAY OF June, 2023  
THAT THE FULL AMOUNT OF THE FEE CHARGED FOR THE PUBLICATION  
OF SAID NOTICE TO WIT \$40.00 ENSURES TO THE  
BENEFITS OF THE PUBLISHER OF SAID NEWSPAPER AND THAT NO  
AGREEMENT AND UNDERSTANDING FOR THE DIVISION THEREOF HAS  
BEEN MADE WITH ANY OTHER PERSON, AND THAT NO PART THEREOF  
HAS BEEN AGREED TO BE PAID TO ANY PERSON WHOMSOEVER.

PUBLISHED ON: 06/02/2023

FILED ON: 06/02/2023

  
SUBSCRIBED AND SWORN TO BEFORE ME THIS 2nd DAY OF June, 2023

NOTARY PUBLIC, SOUTH DAKOTA  
MY COMMISSION EXPIRES 05/23/2029

6/15/23



Ad text : NOTICE OF APPLICATION NO. 8731-3 to Appropriate Water

Notice is given that Gary Stapelman, 724 E Shadow Creek Ln, Sioux Falls SD 57108 has filed an application for a water permit to appropriate 1.67 cubic feet of water per second (cfs) from one well to be completed into the Lower Vermillion Missouri Aquifer (approximately 200 feet deep) located in the approximate center of SW 1/4 Section 3 for irrigation of 162 acres located in the SW 1/4 Section 3; all in T93N-R51W. This site is located approximately 9 miles northeast of Vermillion SD.

Pursuant to SDCL 46-2A-2, the Chief Engineer recommends APPROVAL of Application No. 8731-3 with qualifications because 1) unappropriated water is available, 2) existing domestic water uses and water rights will not be unlawfully impaired, 3) it is a beneficial use of water, and 4) it is in the public interest as it pertains to matters within the regulatory authority of the Water Management Board. The Chief Engineer's recommendation with qualifications, the application, and staff report are available at <https://danr.sd.gov/public> or contact Ron Duvall for this information, or other information, at the Water Rights Program address provided below.

Any person interested in opposing this application or recommendation shall allege that the application, upon approval, will cause injury to the person that is unique from any injury suffered by the public in general. The injury must concern a matter either within the regulatory authority found in SDCL 46-2A-9 for approval or denial of the application, or other matter concerning the application within the regulatory authority of the board to act upon as defined by SDCL 46-2-9 and 46-2-11, or both. Any person meeting the petitioner requirements and wishing to be a party of record in a contested case hearing shall file a written petition to oppose the application with BOTH the applicant and Chief Engineer. A petition opposing the application shall be filed on a form provided by the Chief Engineer. The petition form is available online at <https://danr.sd.gov/public> or by contacting the Chief Engineer. The Chief Engineer's address is "Water Rights Program, Foss Building, 523 E Capitol, Pierre SD 57501" or call (605) 773-3352. The applicant's mailing address is given above. If contesting the Chief Engineer's recommendation, the applicant shall also file a petition. A petition filed by either an interested person or the applicant must be filed by June 12, 2023.

The petition shall include a statement describing the unique injury upon approval of the application on the petitioner, the petitioner's reasons for opposing the application, and the name and mailing address of the petitioner or the petitioner's legal counsel, if legal counsel is obtained.

Any interested person may file a comment on the application with the Chief Engineer. The comment shall be filed on a form provided by the Chief Engineer and is available online at <https://danr.sd.gov/public> or by calling (605) 773-3352 or writing the Chief Engineer at the address provided above. Filing a comment does not make the commenter a party of record or a participant in any hearing that may be held. Any comment must be filed by June 12, 2023.

If the applicant does not contest the recommendation of the Chief Engineer and no petition to oppose the application is received, the Chief Engineer shall act on the application pursuant to the recommendation with no hearing held before the Water Management Board. If a petition opposing the application or contesting the recommendation is filed, then a hearing will be scheduled, and the Water Management Board will consider this application. Notice of the hearing will be given to the applicant and any person filing a petition.

Published once at the total approximate cost of \$40.00 and can be viewed free of charge at [www.sdpublicnotices.com](http://www.sdpublicnotices.com).

Published on June 2, 2023.

## Rodriguez, Rachel

---

**From:** Rodriguez, Rachel  
**Sent:** Tuesday, May 23, 2023 11:37 AM  
**To:** 'debstapelman51@gmail.com'  
**Subject:** 8731-3 Gary Stapelman - Public Notice  
**Attachments:** 8731-3.pdf; Ltr.pdf; 8731-3 public.short\_final.docx

Attached is a copy of the report, chief engineer recommendation and information regarding the public notice for your water permit application. As stated in the letter, **please contact the paper(s) as soon as possible to authorize publication and arrange for payment.** This information is being mailed to you today.

Thank you,

Rachel Rodriguez  
DANR | Program Assistant  
Rachel.Rodriguez@state.sd.us





**DEPARTMENT of AGRICULTURE  
and NATURAL RESOURCES**

JOE FOSS BUILDING  
523 E CAPITOL AVE  
PIERRE SD 57501-3182  
danr.sd.gov

**JUL 11 2023**

Gary Stapelman  
724 E Shadow Creek Ln  
Sioux Falls SD 57108

Dear Mr. Stapelman:

Enclosed is Water Permit No. 8731-3 authorizing construction of the water diversion system and beneficial use of the water, not exceeding the limits as specified in the Water Permit.

Form 10, *Notice of Completion of Works and Application of Water to Beneficial Use*, is enclosed. Please return this completed form after you have finished the system and have put the water to beneficial use. An investigation can then be scheduled so the water license may be issued, thus completing the acquisition of a water right.

An informational sheet *Common Water Right Questions* is also enclosed. This sheet is intended to answer some of the questions associated with obtaining and keeping a water right.

Sincerely,

Eric Gronlund, Chief Engineer  
Water Rights Program  
(605) 773-3352

enclosures



**DEPARTMENT of AGRICULTURE  
and NATURAL RESOURCES**

JOE FOSS BUILDING  
523 E. CAPITOL AVE  
PIERRE SD 57501-3182  
danr.sd.gov

STATE OF SOUTH DAKOTA       )  
                                          ) SS  
COUNTY OF HUGHES         )

**Affidavit of Public Notice  
on DANR Website**

Pursuant to SDCL § 46-2A-4, public notice of the following application was posted on the DANR web site at <https://danr.sd.gov/public>. The posted public notice is the same notice as published in the pertinent newspaper(s) and a copy of the public notice is maintained in the application file. If the application is contested, the posting is moved to the DANR contested case website at <https://danr.sd.gov/public/ContestedCase.aspx> until final action is taken on the application pursuant to SDCL § 46-2A-4.

**Application No.:** 8731-3

**Name of Applicant:** Gary Stapelman

**Date of Posting:** 5/30/2023

**Date of Removal:** 7/11/2023

  
\_\_\_\_\_  
Ron Duvall, Water Rights Permitting Administrator

7/14/23  
\_\_\_\_\_  
Date

Subscribed and sworn to before me, a notary public, this 14 day of July, 2023.

  
\_\_\_\_\_  
Notary Public - South Dakota  
My commission expires:  
**Rachel Rodriguez**  
**My Commission Expires**  
**May 16, 2029**



\_\_\_\_\_  
(SEAL)



DEPARTMENT of AGRICULTURE  
and NATURAL RESOURCES  
JOE FOSS BUILDING  
523 E. CAPITOL AVE  
PIERRE SD 57501-3182  
danr.sd.gov

January 14, 2025

**NOTICE**

TO: MATT ADAMS, OPERATOR, 29533 476TH AVE, BERESFORD, SD 57004

FROM: Ron Duvall, Engineer III  
for Eric Gronlund, Chief Engineer  
Water Rights Program

SUBJECT: Reporting Requirement for 2024 Irrigation Questionnaire(s)

Our records indicate your 2024 Irrigation Questionnaire(s) has not been submitted for Permit No(s) 8731-3. The request for the Questionnaire was dated October 23, 2024. The Water Management Board has directed owners of water permits who have not submitted the 2024 Irrigation Questionnaire(s) be given notice of permit violation and a hearing to be held by the Board. The hearing is to determine what action is to be taken for violation of Water Permit No(s) 8731-3 qualification:

"This permit is approved subject to the Irrigation Water Use Questionnaire being submitted each year."

The hearing will be held on **Wednesday, March 5, 2025, at 9:30 am (Central Time)** in the Floyd Matthew Training Center, Joe Foss Building, 523 E Capitol Avenue, Pierre, SD and will be conducted pursuant to SDCL 46-1-12, 46-1-14, 46-2-9, 46-2-11 and 46-2-17. These are contested case hearings pursuant to Chapter 1-26. According to SDCL 46-1-12, the Board may suspend a permit for a period of up to one year for the first violation of a permit qualification or up to three years for a second violation or cancel a permit for a third violation. Following the hearing, the Water Management Board can:

1. Suspend or cancel Permit No(s) 8731-3 in accordance with applicable provisions of SDCL 46-1-12;
2. Postpone any action; or
3. Take no action.

The hearing is an adversary proceeding. The permit owner has the right to be present or to be represented by a lawyer. These and other due process rights will be forfeited if they are not exercised. Decisions of the Board may be appealed to the Circuit Court and the State Supreme Court as provided by law.

If the questionnaire(s) is (are) received in this office before the **March 5, 2025**, hearing you will no longer be in violation of your permit and your name will be removed from the Board agenda. Enclosed are additional questionnaire(s) for your use. If you have questions or need assistance, please contact Amanda Dewell at (605) 773-3352 or email at [amanda.dewell@state.sd.us](mailto:amanda.dewell@state.sd.us). **If you prefer, you can complete the questionnaire online at the following link: <https://danr.sd.gov/iq> using this password: JHEMRX**

**cc: GARY STAPELMAN; 724 E SHADOW CREEK LN, SIOUX FALLS SD 57108**

**NOTE:** Please contact the Water Rights Program, Joe Foss Building, 523 E Capitol, Pierre, SD (605-773-3352) to assure access to the meeting room for the handicapped or to obtain an interpreter for the hearing impaired.



**DEPARTMENT of AGRICULTURE  
and NATURAL RESOURCES**

JOE FOSS BUILDING  
523 E. CAPITOL AVE  
PIERRE SD 57501-3182  
danr.sd.gov

February 4, 2025

8731-3

Matt Adams  
29533 476<sup>th</sup> Ave  
Beresford SD 57004

Dear Mr. Adams:

I am writing to acknowledge the receipt of your 2024 irrigation questionnaire(s).

You may disregard the January 14, 2025, "Notice" concerning the reporting requirements for Water Permit No(s). 8731-3. The information was received prior to the March 5, 2025, Water Management Board meeting and the above listed permit number(s) have been removed from the agenda.

If you have any questions or concerns, please contact me.

Sincerely,

Amanda Dewell  
Permitting Administrator  
Water Rights Program  
605 773-3352  
Amanda.Dewell@state.sd.us

cc: GARY STAPELMAN; 724 E SHADOW CREEK LN, SIOUX FALLS SD 57108

NOTICE OF COMPLETION OF WORKS AND  
APPLICATION OF WATER TO BENEFICIAL USE

Date 12-04-2025

MAIL TO: PMB 2020  
DANR - Water Rights Program  
523 E. Capitol Ave  
Pierre, SD 57501-3182  
  
Phone: (605) 773-3352

FROM: Gary Stapelman  
(name)

724 E. Shadow Creek Ln.  
(address)

Sioux Falls  
(city)

SD  
(state)

57108  
(zip)

109  
402-707-7132  
(phone)

I have completed the construction of the water use system and I have put the water to beneficial use to the maximum extent it is going to be used.

Water Permit No. 8731-3 states that the water use system is to be constructed by

June 12, 2028, and water is to be put to beneficial use by June 12, 2032.  
(date) (date)

The water use system was completed on June 2024.  
(date)

Applying the water to beneficial use was completed on June 2024.  
(date)

You may schedule an investigation so that the water license may be issued.

Gary Stapelman  
(signature)



**Report of Examination of Works and/or Application of Water to Beneficial Use  
For Permit No. 8731-3**

I have this day, November 18, 2025, made a thorough examination of the water use systems owned by Gary Stapelman, 724 E Shadow Creek Ln., Sioux Falls, SD 57108, holder of Permit No. 8731-3, bearing the priority date of March 15, 2023. This permit authorizes the diversion of 1.67 cu. ft. per second of the waters of groundwater (Lower Vermillion Missouri Aquifer) authorizing the irrigation of 162 acres located in Clay County.

Inspection contacts: Gary Stapelman and Matthew Adams

**A. Works used to divert the water:**

**Well Information**

- 1) Well Drilling Firm: Christensen Well & Irrigation
- 2) No. of Wells: 1
- 3) Depth(s): 178 feet
- 4) Well log is available: Yes

**Casing:**

- 1) Diameter: 16 inches
- 2) Length: 118 feet
- 3) Type: Plastic

**Screen:**

- 1) Diameter: 16 inches
- 2) Length: 60 feet
- 3) Type: PVC
- 4) Static water level: 98 feet

**Pump:**

- 1) Make: Layne & Bowler Vertiline
- 2) Model: 12 KLO
- 3) Capacity: 800 GPM

**Motor:**

- 1) Make: US
- 2) Model No.: HF70
- 3) Horsepower rating: 60 hp

**B. Works used to transport water to place of use:**

- 1) Type: Aluminum      Size: 8 inches      Length: 15 feet

**C. Works used to apply water to beneficial use:**

**Center Pivot:**

- 1) Make: Reinke
- 2) Overall length: 1,153 feet
- 3) Number of towers: 8
- 4) End gun: Yes Range: 100 feet
- 5) Capacity: 700 GPM

**Chemigation Equipment:**

- 1) Does chemigate: No

**D. Compliance with Permit Requirements:**

- 1) Permit qualifications being abided by: Yes  
2) Irrigation Questionnaires checked to determine if permit owner started irrigation by the end of construction period: Yes  
3) Exceptions to compliance are: None

**E. Condition and Location:**

- 1) The system is in good condition with the point(s) of diversion located as follows:  
The well is 1,320 feet north and 1,330 feet east of the southwest corner of Section 3-T93N-R51W (Latitude 42.89902, Longitude -96.86004— approximate center of the SW1/4).  
2) The works are capable of diverting and conveying to the places of use 1.78 cu. ft. per second of water from the well which is to be used for irrigation purposes. Water has been put to beneficial use to the maximum extent as follows:

| <u>Section 3-T93N-R51W</u> |                 |
|----------------------------|-----------------|
| <u>NW1/4SW1/4</u>          | <u>28 acres</u> |
| <u>NE1/4SW1/4</u>          | <u>28 acres</u> |
| <u>SW1/4SW1/4</u>          | <u>29 acres</u> |
| <u>SE1/4SW1/4</u>          | <u>29 acres</u> |

comprising a total of 114 acres of land and the license should be issued for 1.63 cfs.

- 3) All structures, wells and lands on map: Yes



**F. Comments or other permit(s) associated with the project: The pump is rated for 1.78 cfs, but the pivot is nozzled for 1.56 cfs.**

*Keith DeJong*

Keith DeJong, PE Ret.  
Water Rights Inspector  
DANR, Water Rights Program

Date report completed: December 3, 2025

# Water Permit No. 8731-3



*Keith DeJong*  
Keith DeJong, PE Ret.  
Staff Engineer  
November 18, 2025



**DEPARTMENT of AGRICULTURE  
and NATURAL RESOURCES**

JOE FOSS BUILDING  
523 E. CAPITOL AVE  
PIERRE SD 57501-3182  
danr.sd.gov

04/27/2026

8731-3

Gary Stapelman  
724 E Shadow Creek Ln  
Sioux Falls, SD 57108

Dear Mr. Shubeck:

Enclosed is Water License No.8731-3. This is the final water right document completing your process of obtaining a Water Right. Included with your license is a map prepared by the staff engineer who conducted the field investigation.

For your information SDCL 46-6-27 requires that if in the future, the owner of an existing well, constructs a replacement well and does not plan to use the old well, the old well is considered abandoned and must be plugged. Also, any well that is being used or is not considered abandoned must be valved and controlled, if flowing, or sealed and capped so that no leaking occurs either underground or at the surface.

So long as you use the water beneficially, as stated in the Water License, State Water Laws provide that you have a continuing right to use the water. If you have any questions, please contact Amanda Dewell, Permitting Administrator (605) 773-3352.

Sincerely,

Adam Mathiowetz, PE  
Acting Chief Engineer  
Water Rights Program

Enclosures

**STATE OF SOUTH DAKOTA  
WATER LICENSE NO. 8731-3**

---

(1) Gary Stapelman, 724 E Shadow Creek Ln, Sioux Falls, SD 57108, made Application No. 8731-3, March 15, 2023, for a water permit to divert 1.67 cubic feet of water per second from groundwater, one well, (Lower Vermillion Missouri Aquifer), Clay County, for irrigation purposes. Permit No. 8731-3, with a priority date of March 15, 2023, was approved on June 12, 2023, and issued to the applicant for diversion of water with construction of the described water supply system to be completed on or before June 12, 2028, and for the application to beneficial use of water on or before June 12, 2032.

The permit holder submitted a Notice of Completion of Works and Application of Water to Beneficial Use form on December 4, 2025. The Notice stated the diversion system was completed and the water was placed to beneficial use on June 1, 2024.

(2) It is certified that the permit holder has complied with the provisions of South Dakota State Law relating to completion of the construction of the water supply system and is entitled to divert 1.63 cubic feet of water per second for beneficial use. The location of the diversion point is:

- 1320 ft N & 1330 ft E of the SW corner Section 3-T93N-R51W (approximate center of the SW ¼)  
(Latitude 42.89902 & Longitude -96.86004)

(3) The amount of the appropriation may not exceed 2-acre feet annually for each acre of land to which water is actually and beneficially applied for irrigation purposes. The water is to be used during the following described annual period: May 1 – October 31.

(4) The permit holder has complied with the provisions of South Dakota State Law relating to the application of water to beneficial use to irrigate the following land:

Section 3-T93N-R51W  
NE ¼ SW ¼    28 acres              SW ¼ SW ¼    29 acres  
NW ¼ SW ¼    28 acres              SE ¼ SW ¼    29 acres  
TOTAL: 114 acres

(5) Pursuant to South Dakota Water Law 46-5-30. I, Gary Stapelman, the holder and/or owner of Water Right No. 8731-3 is issued a license to appropriate water, the right to use 1.63 cubic feet of water per second, from groundwater, one well, (Lower Vermillion Missouri Aquifer), with a priority date of March 15, 2023, from the location specified in (2) of this license for irrigation purposes.

This license is subject to South Dakota Water Law, any limitations or conditions listed in Water Right No. 8731-3 and subject to the following qualifications:

1. The well approved under Water Permit No. 8731-3 is located near domestic wells and other wells which may obtain water from the same aquifer. Water withdrawals shall be controlled so there is not a reduction of needed water supplies in adequate domestic wells or in adequate wells having prior water rights.

*continued*

2. The well authorized by Permit No. 8731-3 shall be constructed by a licensed well driller and construction of the well and installation of the pump shall comply with Water management Board Well Construction Rules, Chapter 74:02:04 with the well casing pressure grouted (bottom to top) pursuant to Section 74:02:04:28. *(The well was drilled by Christiansen Well & Irrigation in 2023. A copy of the Well Completion Report is on file with the Water Rights Program.)*
3. This Permit is approved subject to the irrigation water use questionnaire being submitted each year.

*Adam Mathiowetz*

Adam Mathiowetz, PE  
Acting Chief Engineer  
Department of Agriculture and Natural Resources

*04/27/2026*

date

