

WATER PERMIT NO. 8760-3

Name of Applicant: Bottolfson Brothers

Address: 46003 Timber Rd, Vermillion SD 57069

Phone: 605-677-9582

Amount of Water Claimed: 2.22 cfs

Total Acres: 172

Source of Water Supply: Groundwater

Water to be used for: Irrigation

County: Clay

Type of Waste Disposal System:

Location: 5 miles north of Vermillion SD

PRIORITY

Date Received: 5-8-2023

Application/License Fee: \$1,050.00

Corrected Application Received:

Period of Annual Use: May 1 – September 30

Remarks:

Diversion Point: SW 1/4 NE 1/4 Section 24 -T93N-
52W


Land to be Irrigated: NE 1/4, SE 1/4 Section 24 -
T93N-R52W

Depth of Well: 120

Well Driller: Heine Electric & Irrigation

Remarks:

Type of Map: aerial



Reviewed and the Number Assigned on: 5-8-2023

By: Rachel Rodriguez

Notice of Hearing - date to intervene: _____

**SOUTH DAKOTA
WATER PERMIT NO. 8760-3**

Date of first receipt of application May 8, 2023.

The Chief Engineer, on behalf of the Water Management Board, issues Water Permit No. 8760-3 to Bottolfson Brothers, c/o Mark Bottolfson, 46003 Timber Road, Vermillion SD 57069 authorizing the construction of the water use system and the placing of water to beneficial use subject to the following limitations, conditions and qualifications:

1. Water Permit No. 8760-3 appropriates 2.22 cubic feet of water per second (cfs) from one well to be completed into the Lower Vermillion Missouri Aquifer (approximately 120 feet deep) located in the SW 1/4 NE 1/4 Section 24 for irrigation of 172 acres located in the NE 1/4, N 1/2 SE 1/4 Section 24; all in T93N-R52W. This site is located approximately 5 miles north of Vermillion SD.
2. The amount of the appropriation may not exceed 2 acre feet annually for each acre of land to which water is actually and beneficially applied for irrigation. The water is to be used during the following described annual period: May 1 – September 30.
3. The date from which applicant may claim right is May 8, 2023.
4. The date of approval of Permit No. 8760-3 is July 31, 2023.
5. One-fifth of the construction is to be completed on or before January 31, 2026.
6. All construction is to be completed on or before July 31, 2028.
7. Water is to be put to beneficial use on or before July 31, 2032.
8. Water rights obtained in compliance with the laws of the State of South Dakota may not be unlawfully impaired by this appropriation.


QUALIFICATIONS

1. The well approved under Water Permit No. 8760-3 is located near domestic wells and other wells which may obtain water from the same aquifer. Water withdrawals shall be controlled so there is not a reduction of needed water supplies in adequate domestic wells or in adequate wells having prior water rights.
2. The well authorized by Permit No. 8760-3 shall be constructed by a licensed well driller and construction of the well and installation of the pump shall comply with Water Management Board Well Construction Rules, Chapter 74:02:04 with the well casing pressure grouted (bottom to top) pursuant to Section 74:02:04:28.
3. This Permit is approved subject to the irrigation water use questionnaire being submitted each year.

WATER MANAGEMENT BOARD

By: Eric Gronlund
Eric Gronlund, Chief Engineer
Water Rights Program
Department of Agriculture and Natural Resources

AUG 31 2023
date



MAY 08 2023

Mail to: DENR - Water Rights 523 E Capitol Ave Pierre, SD 57501-3182 ph. (605) 773-3352	No. <u>8760-3</u> (office use only) Hydrologic Unit <u>10170102</u>
	Basin <u>Vermillion</u>
	Newspaper <u>Plain Talk</u>
	<u>Daily Press & Dakotan</u>

OFFICE OF
WATER

PAID

MAY 08 2023

 Clk# 2408
 Rec't# 05-08-23

Application For Permit To Appropriate Water For Irrigation

 Type of Application: ☒ New ☐ Vested Right ☐ Amendment/Correction to Permit No. _____
 (Use predates Mar 2, 1955)

Description of amendment/correction: (i.e. change diversion point(s), add diversion point(s), change use, etc.)

 1. Name to Appear on Irrigation Permit Bottolfson Brothers

Note: The "Name to Appear on Irrigation Permit" must be the name in which the property to be irrigated is held in.

 Mailing Address 46003 Timber Rd Vermillion SD 57069
 (Address) (City) (State) (Zip Code)

 Phone _____ Mobile 605-677-9582 Email bottolfson64@hotmail.com

 2. Amount of water claimed 2.22*CFS or 1000 **GPM ***AF Total Acreage 172
 (*Cubic Feet per Second) (**Gallons per Minute) (***)Acre Feet - storage capacity of dam/dugout or annual use if applicable)

 3. Source of water supply Ground water (1 well)

 4. Location of point of diversion 1 well in SWNE T93N R52W S24
 (example - 3 wells in SW1/4 NE1/4 section 12-T104N-R53W)

County _____

 5. County or counties where water will be used Clay

 6. Annual period during which water is to be used May 1 - September 30

 7. List below each forty acre division, or lot, or fraction thereof and show number of acres to be irrigated in each.
 (Attach sheet if more space is needed)

Land Description	Acres	Land Description	Acres
NWNE T93N R52W S24	38	NWSE T93N R52W S24	37
NENE T93N R52W S24	25	NESE T93N R52W S24	16
SWNE T93N R52W S24	30		
SENE T93N R52W S24	26		

8. Give a description of the project. (Attach sheet if more space is needed)

1 well in SWNE T93N R52W S24 to supply water to a center pivot

 I, Mark Bottolfson
 Name of Person

Owner / partner, the applicant, certify under
 Title (if applicable)

penalty of perjury that I have read this application, examined the attached map, and that the matters stated are true. I further certify, if acting on behalf of an entity or individual other than myself, that I am authorized to submit this application.

Supplemental Information

(type or print)

1. Well Information (check one or both as applicable) ☒ Drilling new well(s) ☐ Using existing well(s)a) If new wells, how many 1 Have test holes been drilled ☒ Yes ☐ No Drilled by Heine Electric + Irrigation
(if yes, please provide copies of logs)b) If existing wells, how many Provide copy of log(s), if available. Drilled by

For either Existing or Proposed Wells:


c) Well Depth (required) ~120 Depth to Top of Water Bearing Material ~93 Depth to Water from Surface ~70d) Distance to nearest domestic well on applicant's property N/A Property owned by others NO**2. Wastewater Disposal System Information**a) Type of System (i.e. septic tank, drain field) b) System Capacity (gallons) Year Constructed c) Connected to the City of Sanitary System **3. Dugout Information**a) Surface Dimensions Depth b) Depth to water (ground surface to water level) **4. Water Storage Dams**

If the proposed water use system contains one or more storage dams, please furnish the information requested below for each dam. The locations of the dams need to be shown on the map submitted with the application.

- a) If a private engineering firm or government agency was involved in the design of this dam, please give their name and address:

b) Freeboard c) Crest Width Crest Length d) Height e) Primary Outlet Capacity If pipe, diameter f) Secondary Spillway Capacity Spillway Width

g) X & Y Slope (e.g. 3 to 1 is a typical slope)

Upstream Downstream h) Surface Area of Impoundment i) Storage Acre Feetj) Drainage Area Above Dam Acres




Map Summary Report - Bottolfson - West WW



Project Name - Mark Bottolfson - Macy Ferris WW

Version Name - Mark Bottolfson - Macy Ferris WW_Version



HEINE ELECTRIC & IRRIGATION - 307 S. Robinson Ave, Hartington, NE, 68739-5139, United States

Water Well Completion Reports



SEARCH WELLS
Help Tools

DRILLERS

PUMP INSTALLERS

Disclaimer



Search

312th St
SWNE T93N R52W S24

X Proposed well

T093N R052W S23

T093N R052W S24

Hwy 19

Hwy 19 Ave

T093N R052W S26

T093N R052W S25

Streets

Show Search Results

8760-3

SD EForm - 1621LD V1


SOUTH DAKOTA WATER WELL COMPLETION REPORT

11-02

Location SW ¼ NE ¼ Sec 24 Twp 93N Rg 52W

County CLAY

Please mark well location with an "X"



Well Completion Date

4-28-2023

1 Mile

Distance to nearest potential pollution source (septic tank, abandoned well, feed lot, etc.)?
ft. from (identify source)

PROPOSED USE:

☐ Domestic/Stock ☐ Municipal ☐ Business ☒ Test holes
☐ Irrigation ☐ Industrial ☐ Institutional ☐ Monitoring well
METHOD OF DRILLING:
ROTARY

CASING DATA:

☐ Steel ☒ Plastic ☐ Other

If other describe

PIPEWEIGHT	DIAMETER	FROM	TO	HOLE DIAMETER
LB/FT	IN	FT	FT	5.25 IN
LB/FT	IN	FT	FT	IN
LB/FT	IN	FT	FT	IN

GROUTING DATA:

Grout Type	No. of Sacks	Grout Weight	From	To
Groutwell DF	65	Lb/gal	1 Ft	116 Ft
		Lb/gal	Ft	Ft

Describe grouting procedure
TREMME

SCREEN:

☐ Perforated pipe ☐ Manufactured

Diameter _____ Inches Length _____ Feet

Material _____

Slot Size _____ Set From _____ Feet to _____ Feet

Other information _____

WAS A PACKER OR SEAL USED? ☐ Yes ☒ No

If so, what material?

Describe packer(s) and location

DISINFECTION: Was well disinfected upon completion?

☐ Yes, How?☒ No, Why Not? TEST HOLE

Lab to which water quality sample sent for analysis

Well Owner: MARK BOTTOLFSON

Business Name:

Address: 46003 TIMBER RD

City, State, Zip: VERMILLION SD 57069

WELL LOG:

FORMATION	DEPTH	
	FROM	TO
TOP SOIL	0	3
GLACIAL TILL	3	15
GRAY SANDY CLAY	15	78
FINE GRAY SAND WITH CLAY	78	85
FINE TO MEDIUM SAND	85	93
FINE TO MEDIUM SAND & GRAVEL	93	116

STATIC WATER LEVEL

FEET

If flowing: closed in pressure _____ PSI

GPM flow _____ through _____ Inch pipe

Controlled by ☐ Valve ☐ Reducers ☐ Other

Reduced flow rate _____ GPM

Can well be completely shut in?

WELL TEST DATA:

☐ Pumped Describe:☐ Bailed☐ Other

Pumping Level Below Land Surface

_____ Ft. After _____ Hrs. pumped _____ GPM

_____ Ft. After _____ Hrs. pumped _____ GPM

If pump installed, pump rate: _____ GPM

REMARKS

LATITUDE: 42.860929

LONGITUDE: -96.9328

ELEVATION: 1196

RECEIVED

JUL 06 2023

OFFICE OF
WATER

This well was drilled under license # 810 and this report is true and accurate.

Drilling firm: HEINE ELECTRIC & IRRIGATION, INC.

Signature of License Representative:

Signature of Well Owner or Equitable Property Holder:

Date: 7-6-23

RECEIPT

WATER RIGHTS PROGRAM South Dakota Department of Agriculture and Natural Resources

Date May 8, 2023

RECEIVED OF Bottolfson Brothers 46003 Timber Rd., Vermillion SD 57069

The following amount in fees for services rendered as provided for by law:

Fee for Application for Permit No. <u>8760-3</u> to Appropriate Water, to construct and to put water to beneficial use	<u>\$850.00</u>
Fee for Application for Permit No. _____ to Appropriate Water for Future use	\$ _____
Fee to retain Future Use Permit No. _____ after period of seven years.	\$ _____
Fee for Inspecting Constructed Works, confirming beneficial use and issuing Water License No. <u>8760-3</u>	<u>\$200.00</u>
Fee for Filing Transfer Form _____	\$ _____
Fee for _____	\$ _____
Fee for Issuing New Well Driller's License No. _____	\$ _____
Fee for Renewal of Well Driller's License No. _____	\$ _____
Fee for Issuing Well Pump Installer's License No. _____	\$ _____
Fee for Renewal of Well Pump Installer's License No. _____	\$ _____
(Any Other Work Provided by Law) TOTAL	<u>\$1050.00</u>

By Eric Gronlund
Chief Engineer
Em



**DEPARTMENT of AGRICULTURE
and NATURAL RESOURCES**

JOE FOSS BUILDING
523 E. CAPITOL AVE
PIERRE SD 57501-3182
danr.sd.gov

**RECOMMENDATION OF CHIEF ENGINEER FOR WATER PERMIT
APPLICATION NO. 8760-3, Bottolfson Brothers**

Pursuant to SDCL 46-2A-2, the following is the recommendation of the Chief Engineer, Water Rights Program, Department of Agriculture and Natural Resources concerning Water Permit Application No. 8760-3, Bottolfson Brothers, 46003 Timber Road, Vermillion SD 57069.

The Chief Engineer is recommending APPROVAL of Application No. 8760-3 because 1) there is reasonable probability that there is unappropriated water available for the applicant's proposed use, 2) the proposed diversion can be developed without unlawful impairment of existing domestic water uses and water rights, 3) the proposed use is a beneficial use and 4) it is in the public interest as it pertains to matters of public interest within the regulatory authority of the Water Management Board with the following qualifications:

1. The well approved under Water Permit No. 8760-3 is located near domestic wells and other wells which may obtain water from the same aquifer. Water withdrawals shall be controlled so there is not a reduction of needed water supplies in adequate domestic wells or in adequate wells having prior water rights.
2. The well authorized by Permit No. 8760-3 shall be constructed by a licensed well driller and construction of the well and installation of the pump shall comply with Water Management Board Well Construction Rules, Chapter 74:02:04 with the well casing pressure grouted (bottom to top) pursuant to Section 74:02:04:28.
3. This Permit is approved subject to the irrigation water use questionnaire being submitted each year.

See report on application for additional information.

Eric Gronlund, Chief Engineer
July 6, 2023

Report to the Chief Engineer
On Water Permit Application No. 8760-3

Bottolfson Brothers

June 23rd, 2023

Water Permit Application No. 8760-3 proposes to appropriate 2.22 cubic feet of water per second (cfs) from one well to be completed into the Lower Vermillion Missouri aquifer (approximately 120 feet deep) located in the SW ¼ NE ¼ Section 24 for irrigation of 172 acres located in the NE ¼, N ½ SE ¼ Section 24; all in T93N-R52W. The site of interest is located approximately 5 miles north of Vermillion, SD in Clay County.

AQUIFER: Lower Vermillion Missouri (LVM)

HYDROGEOLOGY:

The Lower Vermillion Missouri aquifer, referred to as the LVM aquifer for the remainder of this report, is a buried glacial outwash that was deposited by meltwater streams beyond the margin of active glacial ice (Stephens, 1967). The LVM aquifer materials range in size from a coarse sand to a coarse gravel (Niehus, 1994). The LVM aquifer is primarily confined but can be locally found under unconfined conditions such as in the flood plain of the Vermillion River (Niehus, 1994; Stephens, 1967). The LVM aquifer has an average thickness of approximately 100 feet in Clay County (Stephens, 1967). Table 1 shows the information related to the areal extent of the LVM aquifer, the area utilized for this report is approximately 106,000 acres (Mathiowetz, 2018).

Table 1. Estimated areal extent for the historic LVM aquifer boundary (Hedges and others, 1982), the portion of the UVM:S aquifer that overlies the historic LVM aquifer boundary (Buhler, 2014). The current LVM aquifer boundary (Mathiowetz, 2018), and the unconfined portion of the LVM aquifer along the Vermillion River (modified from Jensen, 2000; modified from Stonesifer, 2013).

Delineation	Estimated Areal Extent (acres)
Historic Lower Vermillion Missouri Aquifer (modified from Hedges and others, 1982)	124,000
Upper Vermillion Missouri: South Aquifer (UVM:S) (modified from Buhler, 2014) - Portion that overlies LVM aquifer boundary estimated by Hedges and others, 1982.	18,000
Current Lower Vermillion Missouri Aquifer* (Mathiowetz, 2018)	106,000
Unconfined Portion of Lower Vermillion Missouri Aquifer - not enclosed in UVM:S (Buhler, 2014) (modified from Jensen, 2000; modified from Stonesifer, 2013)	12,000
*Estimated by subtracting UVM:S aquifer boundary (Buhler, 2014) from historic boundary (Hedges and others, 1982)	

The LVM aquifer is hydrologically connected to the Upper Vermillion Missouri: South (UVM:S) aquifer to the north, the Missouri: Elk Point aquifer to the south, the underlying Dakota aquifer, and the Vermillion River (Buhler, 2014; Mathiowetz, 2018; Niehus, 1994; Stephens, 1967). Hedges and others (1982) delineated a boundary between the Upper Vermillion Missouri aquifer and LVM aquifer with portions of each boundary being modified by Buhler (2014) and Mathiowetz (2018) in response to additional study of the Upper Vermillion Missouri aquifer, as shown on Figure 1.




Figure 1. Map of the approximate LVM aquifer boundary delineated by Hedges and others (1982) with a portion of the UVM:S and LVM aquifer boundary estimated by Buhler (2014) and Mathiowetz (2018) respectively, and the location of proposed diversion point for Water Permit Application No. 8760-3, and LVM aquifer observation wells and water rights (Water Rights, 2023b and 2023c).

A test hole completion report was submitted with the application. The test hole is located in the same approximate area as the proposed diversion point and the test hole was completed into the LVM aquifer on April 28th, 2023 (Water Rights, 2023b). The reported depth to the top of aquifer material is 85 feet below the ground surface. A static water level was estimated by looking at the average static water level of nearby water well completion reports near the proposed diversion point. The estimated static water level is approximately 75 feet below the ground surface, which yields an estimated saturated aquifer thickness of approximately 31 feet (SDGS, 2023; Water Rights, 2023b). Based on water well completion reports near the proposed diversion point and

the submitted test hole completion report, the LVM aquifer is expected to be confined at the diversion point (SDGS, 2023; Water Rights, 2023b and 2023d).

South Dakota Codified Law (SDCL) 46-2A-9

Pursuant to SDCL 46-2A-9, “A permit to appropriate water may be issued only if there is a reasonable probability that unappropriated water is available for the applicant’s proposed use, the proposed diversion can be developed without unlawful impairment of existing domestic water uses and water rights, the proposed use is a beneficial use, and the permit is in the public interest as it pertains to matters of public interest within the regulatory authority of the Water Management Board as defined by SDCL 46-2-9 and 46-2-11.” This report will address the availability of unappropriated water and the potential for unlawful impairment of existing domestic uses and water rights within the LVM aquifer.

WATER AVAILABILITY:

Water Permit Application No. 8760-3 proposes to appropriate water from the LVM aquifer for irrigation use. The probability of unappropriated water being available from the aquifer can be evaluated by considering SDCL 46-6-3.1, which requires “No application to appropriate groundwater may be approved if, according to the best information reasonably available, it is probable that the quantity of water withdrawn annually from a groundwater source will exceed the quantity of the average estimated annual recharge of water to the groundwater source. An application may be approved, however, for withdrawals of groundwater from any groundwater formation older than or stratigraphically lower than the greenhorn formation in excess of the average estimated annual recharge for use by water distribution systems.” The LVM aquifer is not older than or stratigraphically lower than the Greenhorn Formation, and the applicant’s proposed use is not for use in a water distribution system as defined by SDCL 46-1-6(17). Therefore, the average annual recharge and average annual withdrawal rates to and from the LVM aquifer must be considered.

HYDROLOGIC BUDGET:

Recharge

Recharge to the LVM aquifer is received primarily through infiltration of precipitation where the aquifer is at or near land surface, groundwater inflow from the Upper Vermillion Missouri: South aquifer, seepage from Vermillion River, and leakage from the underlying Dakota aquifer (Niehus, 1994; Stephens, 1967). Using observation well analysis, Hedges and others (1985) estimated a recharge rate of 3.8 inches per year for the unconfined portion of the LVM aquifer. However, Stonesifer (2013) recalculated the recharge rate to be an estimated 4.58 inches per year using the same method but with additional observation well data. The unconfined area for this primarily confined aquifer is approximately 12,000 acres (Table 1; modified from Jensen, 2000; modified from Stonesifer, 2013). Therefore, the estimated average annual recharge rate for the unconfined portion of the LVM aquifer is approximately 4,580 acre-feet/year (based on Stonesifer, 2013 and modified from Jensen, 2000).

It is assumed that the confined portion of the LVM aquifer is hydrologically similar to the confined portion of the Upper Vermillion Missouri aquifer and recharges at a similar rate. However, further study conducted on the Upper Vermillion Missouri aquifer concluded the Hedges and others (1985) recharge rate estimate to the confined portion of the Upper Vermillion Missouri aquifer is likely underestimated (Holmes & Filipovic, 2015; Buhler, 2014)). Using regional flow-net analysis, Hedges and others (1985) estimated the recharge rate of the, primarily confined, Upper Vermillion Missouri aquifer to be approximately 0.25 inches per year. The confined portion of the LVM aquifer is approximately 94,000 acres, this was found by subtracting the unconfined area from the current total area on Table 1. Using the Hedges and others (1985) confined recharge rate multiplied by the confined portion areal extent, the average annual recharge rate for the confined portion of the LVM aquifer is approximately 1,960 acre-feet per year; keeping in mind that this estimate is likely lower than the actual rate based on Holmes & Filipovic (2015) investigation and Buhler's (2014) report. Combining average annual recharge rate for both the confined and unconfined portions of the LVM aquifer (within the LVM aquifer within Hedges and others (1982) historical aquifer boundary minus Buhler (2014) delineation of the UVM:S aquifer boundary), the average annual recharge rate is approximately 6,540 acre-feet per year.

Discharge

Discharge from the LVM aquifer primarily occurs through well withdrawals, seepage to surface water features, and evapotranspiration in areas where the aquifer is at or near land surface (Niehus, 1994; Water Rights, 2023d). There are 97 water rights/permits authorized to appropriate water from the LVM aquifer within the historical aquifer boundary delineated by Hedges and others (1982) (Water Rights, 2023c). However, 61 water rights/permits are in both the LVM aquifer boundary delineated by Hedges and others (1982) and the Upper Vermillion Missouri: South aquifer boundary delineated by Buhler (2014). Of the 61 water rights/permits, 29 are currently withdrawing water from the Upper Vermillion Missouri: South aquifer and are still labeled as withdrawing water from the LVM aquifer. Therefore, by excluding the 29 water rights/permits that are withdrawing from the Upper Vermillion Missouri: South aquifer from the 97 water rights/permits, there are 68 water rights/permits authorized to appropriate water from the LVM aquifer within the current aquifer boundary delineated by Mathiowetz (2018). There are four other pending applications (Application Nos. 8731-3, 8745-3, 8746-3, and 8747-3) for the LVM aquifer beside this application. There are no future use permits reserving water from the LVM aquifer (Water Rights, 2023c).

Table 2 summarizes the 7 non-irrigation water rights/permits authorized to appropriate water from the LVM aquifer with the estimated annual use for each water right/permit as determined by their limiting diversion rate or annual volume. The data on Table 2 is broken up into two sets of water rights/permits 1) those that are located in the historic aquifer boundary by Hedges and others (1982) but not in the Upper Vermillion Missouri: South aquifer boundary delineated by Buhler (2014) and 2) water rights/permits that are located within both boundaries. The amount of water withdrawn was estimated by assuming the non-irrigation water rights/permits limited by an annual volume will withdraw their entire appropriated volume every year. It is estimated that the

non-irrigation water rights/permits limited only by a diversion rate will pump at their maximum permitted diversion rate for 60 percent of the time. This is a standard method developed by the DANR-Water Rights Program for estimating average annual withdrawals by non-irrigation appropriations limited solely by diversion rate. It is likely an overestimate of water withdrawn by water rights/permits only limited by diversion rate. Application No. 8745-3 is requesting 564 acre-feet of water to be appropriated for a one-time use with the following years of water use being non-consumptive by re-injecting the pumped water back into the aquifer (Water Rights, 2023c). Therefore, the average annual use for this application that will be accounted for in the hydrologic budget for the LVM aquifer will be 0 ac-ft/yr. Overall, the estimated average annual withdrawal rate for the LVM aquifer non-irrigation water rights/permits within the historic aquifer boundary (Hedges and others, 1982) is approximately 1,224.4 acre-feet/year, and approximately 48.6 acre-feet/year excluding water rights/permits that are in the Upper Vermillion Missouri: South delineation by Buhler (2014) (Table 2) (Water Rights, 2023c).

Table 2. Estimated average annual use for non-irrigation water rights/permits authorized to appropriate water from the LVM aquifer within the historic aquifer boundary by Hedges and others (1982) but not the UVM:S aquifer delineation by Buhler (2014), and non-irrigation water rights within aquifer boundary delineated by Hedges and others (1982) and Buhler's (2014) UVM:S boundary (Water Rights, 2023c).

Permit No.	Name	Uses	Status	Authorized Diversion Rate (cfs)	Authorized Annual Volume (acre-feet)	Estimated Use (acre-feet/year)
1870-3	USD FACILITIES MGMT	INS	LC	0.03	NA	13.0
6397-3	SD DEPT OF TRANSPORTATION	INS	LC	0.033	NA	14.3
8222-3	SOUTHEAST FARMERS COOP	COM	PE	0.167	18.4	18.4
8257-3	THEIN WELL CO INC	COM	PE	0.089	1	1
8479-3	KNIFE RIVER	IND	PE	0.133	1.84	1.84
					Total:	48.6
3905-3*	CLAY RURAL WATER SYSTEM INC	RWS	LC	2	NA	868.8
5979-3*	CLAY RURAL WATER SYSTEM INC	RWS	LC	2	307	307
					Total:	1175.8
*Within aquifer boundary delineated by Hedges and others (1982) and Buhler's (2014) UVM:S boundary						
LC Licensed Water Right, PE Water Permit, INS Institutional, COM Commercial, RWS Rural Water System						

There are 90 irrigation water rights/permits appropriating water from the LVM aquifer within Hedges and others (1982) historical aquifer boundary (Water Rights, 2023c). Irrigation water rights/permits have been typically required to report their annual usage on an irrigation questionnaire since 1979. However, due to changes in farming practices, new equipment, and an increase in the number of permits from 43 in 2006 to 71 in 2013, the average over the entire period of record may not be an accurate reflection of average annual irrigation withdrawal at the present time. The average annual withdrawal rate for the LVM aquifer within Hedges and others

(1982) historical boundary for irrigation water rights/permits that have reported over the past ten years of record (2012 to 2021) is approximately 3,015 acre-feet per year (Table 3) (Water Rights, 2023a).

There are 61 irrigation water rights/permits appropriating water from the LVM aquifer within Hedges and others (1982) historical aquifer boundary excluding rights/permits within delineation UVM:S aquifer by Buhler (2014) (Water Rights, 2023c). However, due to changes in farming practices and an increase in the number of permits from 27 in 2006 to 45 in 2013, the average over the entire period of record may not be an accurate reflection of actual average annual withdrawal at the present time. The average annual withdrawal rate for the LVM aquifer irrigation water rights/permits that have reported over the past ten years of record (2012 to 2021) is approximately 1,866 acre-feet per year (Table 3) (Water Rights, 2023a).

There were ten irrigation water permits approved in 2022 and early 2023 (Nos. 8632-3, 8589-3, 8641-3, 8672-3, 8680-3, 8692-3, 8693-3, 8711-3, 8725-3, and 8726-3) and there are four other irrigation applications currently pending in 2023 (Nos. 8731-3, 8746-3, 8747-3, and 8760-3 (this application)) that were not included in the irrigation questionnaire compilation and need to be accounted for. The new permits are authorized to irrigate 1,093 acres, while the pending applications (Nos. 8731-3, 8746-3, 8747-3, and 8760-3 (this application)), propose to irrigate approximately 558 acres. All together a total of 1,651 acres are planned to be irrigated (Water Rights, 2023c). Assuming one foot of water per acre per year, the withdrawal rate for these water permits/applications is approximately 1,651 acre-feet per year. The average annual withdrawal rate for irrigation appropriations from 2012 to 2021 (Table 3) combined with 2022 and 2023 permits and new applications within Hedges and others (1982) historical aquifer boundary, is approximately 4,666 acre-feet per year (Water Rights, 2023a). The average annual withdrawal rate for irrigation appropriations from 2012 to 2021 (Table 3) combined with 2022 and 2023 permits and new applications within Hedges and others (1982) historical aquifer boundary excluding water rights/permits within delineation UVM:S aquifer by Buhler (2014), is approximately 3,517 acre-feet per year (Water Rights, 2023a).

There are domestic wells completed into the LVM aquifer that do not require a water right/permit, so the withdrawal amount from those wells is unknown (Water Rights, 2023d). Due to their relatively low diversion rates, withdrawals from domestic wells are not considered to be a significant portion of the hydrologic budget. Additionally, with the development of rural water systems in areas where the LVM aquifer is the uppermost aquifer available; it is likely some domestic users may have transitioned to rural water. Therefore, the quantity of water withdrawn by domestic wells is estimated to be negligible to the hydrologic budget for the LVM aquifer.

Table 3. Reported irrigation uses from the LVM aquifer for water right/permits within the historical boundary of LVM aquifer excluding delineation UVM:S aquifer (Buhler, 2014) (Water Rights, 2023a)

Historical Boundary of LVM aquifer (Hedges and others, 1982)			Historical Boundary of LVM aquifer (Hedges and others, 1982), Excluding UVM:S Aquifer Boundary (Buhler, 2014)		
Year	Number of Permit/License	Annual Pumpage (ac-ft/yr)	Year	Number of Permit/License	Annual Pumpage (ac-ft/yr)
1979	49	1163.0	1979	40	810.5
1980	47	2417.0	1980	38	1995.0
1981	49	1543.0	1981	39	1205.4
1982	37	870.0	1982	27	758.3
1983	38	716.3	1983	28	644.7
1984	47	691.0	1984	37	549.0
1985	46	1328.2	1985	36	927.2
1986	45	1047.5	1986	35	807.5
1987	37	1115.4	1987	27	794.4
1988	38	2083.8	1988	28	1442.4
1989	38	2301.2	1989	28	1522.2
1990	38	2113.2	1990	28	1288.2
1991	39	1670.1	1991	29	1044.1
1992	39	168.8	1992	29	116.7
1993	39	0.0	1993	29	0.0
1994	39	517.3	1994	29	308.7
1995	37	506.6	1995	28	368.2
1996	36	997.6	1996	27	572.9
1997	36	1085.0	1997	27	645.0
1998	36	1032.9	1998	26	736.6
1999	38	900.6	1999	27	698.9
2000	38	2041.7	2000	27	1574.9
2001	38	2037.0	2001	27	1781.8
2002	40	1762.3	2002	29	1123.2
2003	40	1800.6	2003	29	1470.6
2004	39	1747.5	2004	28	1167.6
2005	45	1410.2	2005	28	1071.1
2006	43	2674.5	2006	27	1734.3
2007	50	2909.1	2007	26	1327.0
2008	55	4301.3	2008	28	911.9
2009	58	482.6	2009	30	460.8
2010	59	144.6	2010	30	134.0
2011	62	2195.1	2011	33	1219.4
2012	61	7759.5	2012	33	3355.3
2013	71	4109.1	2013	45	2856.5
2014	75	1576.3	2014	48	1006.4
2015	78	1925.8	2015	50	1473.5
2016	79	2187.5	2016	51	1779.0
2017	79	3156.6	2017	52	2439.3
2018	79	427.7	2018	52	419.4
2019	79	339.6	2019	52	333.0
2020	78	3353.2	2020	51	1972.5
2021	80	5316.2	2021	54	3026.7
Average 1979-2021		1812.2	Average 1979-2021		1159.9
Average 2012-2021		3015.2	Average 2012-2021		1866.2

Hydrologic Budget Summary

The average annual recharge rate for the unconfined portion of the LVM aquifer not enclosed in the UVM:S aquifer (Buhler, 2014) is approximately 4,580 acre-feet/year. The average annual recharge rate for the current confined portion LVM aquifer (Mathiowetz, 2018) is approximately 1,960 acre-feet/year. Combining average annual recharge rate for both the current confined and unconfined portions of the LVM aquifer not enclosed in the UVM:S aquifer, the average annual recharge rate is approximately 6,540 acre-feet per year.

The average annual withdrawal rate from the LVM aquifer within Hedges and others (1982) historical aquifer boundary (the non-irrigation appropriations (1,224 acre-feet/year); the average annual withdrawal rate for irrigation appropriations from 2012 to 2021, 2022-2023 water permits, and pending applications, including this one, (4,666 acre-feet/year)) is approximately 5,890 acre-feet per year, also shown on Table 4 (Water Rights, 2023a).

The average annual withdrawal rate from the LVM aquifer within Hedges and others (1982) historical aquifer boundary excluding rights/permits within delineation UVM:S aquifer by Buhler (2014) (the non-irrigation appropriations (49 acre-feet/year); the average annual withdrawal rate for irrigation appropriations from 2012 to 2021, 2022-2023 water permits, and new applications, including this one, (3,517 acre-feet/year)) is approximately 3,566 acre-feet per year, also shown on Table 4 (Water Rights, 2023a).

Application No. 8745-3 proposes a one-time use of 564 acre-feet/year with an ongoing non-consumptive use of water due to reinjection of pumped water into the aquifer. Therefore, the one-time use is not included in the average annual use because the annual use will be 0 acre-feet/year.

Collectively, the average annual recharge rate for both the confined and unconfined portions of the LVM aquifer is greater than the average annual withdrawal rate from both the LVM aquifer within Hedges and others (1982) historical aquifer boundary and the LVM aquifer within Buhler (2014) and Mathiowetz (2018) boundary delineated portions of the UVM:S and LVM aquifers. Furthermore, the average annual recharge to the aquifer exceeds the average annual withdrawals plus the one-time use for Application No. 8745-3. Based on the hydrologic budget, there is a reasonable probability unappropriated water is available from the LVM aquifer for the proposed appropriation.

Table 4. List of water rights/permits withdrawals, new applications (if approved), and one-time use for application withdrawals from both the historic boundary of the LVM and current boundary of the LVM excluding the UVM:S delineated areas made by Buhler (2014) (Water Rights, 2023a)

	Historical Boundary of the LVM Aquifer (Hedges and others, 1982) Pumpage (ac-ft/yr)	Historic Boundary of the LVM Aquifer (Hedges and others, 1982), Excluding UVM:S Aquifer Boundary (Buhler 2014) Pumpage (ac-ft/yr)
Non-Irrigation Appropriation	1,224	49
Irrigation Appropriation (2012-2022)	3,015	1,866
New Permits (2022-2023)	1,093	1,093
Pending Applications (Including this one)	558	558
Total	5,890	3,566
Application No. 8745-3 one-time use (2023)	564	564

OBSERVATION WELL DATA:

Administrative Rule of South Dakota (ARSD) 74:02:05:07 requires that the Water Management Board shall rely upon the record of observation well measurements in addition to other data to determine that the quantity of water withdrawn annually from the aquifer does not exceed the estimated average annual recharge of the aquifer.

The DANR-Water Rights Program monitors ten observation wells completed into the LVM aquifer with two additional observation wells (CL-80J and CL-66AR) that are within both the historic aquifer boundary delineated by Hedges and others (1982) and Upper Vermillion Missouri: South aquifer boundary as defined by Buhler (2014), with observation wells in the area of this application shown on Figure 5 (Water Rights, 2023b). These observation wells provide data on how the aquifer reacts to regional climatic conditions and local pumping. The three closest observation wells to the diversion point are CL-80G (approximately 2.4 miles southwest), CL-57A (approximately 3.2 miles south), and CL-80H (approximately 4.1 miles northeast) (Water Rights, 2023b). The hydrographs for these observation wells are displayed in Figures 2, 3, and 4 respectively (Water Rights, 2023b). The data points utilized to construct the hydrographs are measurements of the static water level in the observation wells from the top of the well casing. It is worth noting the hydrograph titles display DENR Water Rights Observation Well on the hydrographs when the titles should display DANR Water Rights Observation Well on the hydrographs.




Figure 2. Hydrograph for observation well CL-80G (Water Rights, 2023b)




Figure 3. Hydrograph for observation well CL-57A (Water Rights, 2023b)




Figure 4. Hydrograph for observation well CL-80H (Water Rights, 2023b)

A majority of the observation wells in the LVM aquifer have a relatively stable trend in the water level, as seen in Figures 2 to 4. Figure 3's water level is much higher than the other figures, this is due to its close proximity to the Vermillion River. The hydrographs for the LVM aquifer observation wells indicate that the aquifer responds well to climatic conditions because water levels are rising during wetter periods (early spring snowmelt and precipitation) and declining to a stable water level during drier periods. Additionally, the water levels in the observation wells display that the amount of recharge to and natural discharge from the aquifer greatly exceeds pumping with the aquifer with water levels returning to pre-pumping conditions between irrigation seasons. Aquifer recovery indicates that climatic conditions and therefore, the effects of recharge to and natural discharges from the aquifer govern the long-term fluctuations of waters levels in the aquifer rather than the impacts of pumping from the LVM aquifer. By recognizing that both recharge to and natural discharge from an aquifer can be captured for pumping, the observation well hydrographs demonstrate unappropriated water is available for the proposed appropriation.

POTENTIAL FOR UNLAWFUL IMPAIRMENT OF EXISTING WATER RIGHTS:

Water rights/permits in the general vicinity of the proposed well site for this application are shown in Figure 5 and summarized in Table 5. Water Right No. 7487-3 is the closest water right to the diversion point; however, Water Right No. 7487-3 is also held by Bottolfson Brothers so the next closest not held by the applicant will be used. The next closest water right/permit to the diversion point for this application, not held by the applicant, is Water Right No. 7472-3 which is held by Paul Bremer. The diversion point for Water Right No. 7472-3 is located approximately 1.2 miles north of the proposed diversion point for this application (Water Rights, 2023c). There are domestic wells on file with the DANR-Water Rights Program that are completed into the LVM aquifer, with the closest domestic well on file (not held by the applicant) approximately 0.5 miles east of the diversion point based on the legal description provided by the well driller on

the well completion report (Water Rights, 2023d). There could potentially be other domestic wells completed into the LVM aquifer near the diversion point that are not on file with the DANR-Water Rights Program.




Figure 5. Map of the proposed diversion point for Water Permit Application No. 8760-3, nearby LVM aquifer water rights/permits, and observation wells within 4 miles of the proposed diversion point (Water Rights, 2023b and 2023c).

Table 5. List of water rights/permits shown in Figure 5 (Water Rights, 2023c).

Permit	Name/Business	Priority	Status	Use Type	CFS	Acres
2966-3	Harold/Beverly Fischer	08/25/1976	License	Irrigation	1.05	74
6985-3	Nels J Sorensen	02/25/2008	License	Irrigation	1.6	112
7082-3	Bottolfson Brothers	10/29/2008	License	Irrigation	1.56	138
7230-3	Paul Bremer	02/09/2011	License	Irrigation	1.33	71
7472-3	Paul Bremer	10/22/2012	License	Irrigation	1.78	134
7477-3	Chad Heckathorn	10/22/2012	License	Irrigation	1.78	115
7487-3	Bottolfson Brothers	10/29/2012	License	Irrigation	1.56	140
7688-3	Nicholas W Olson	02/06/2013	License	Irrigation	0.47	33
8459-3	Paul Bremer	11/18/2020	Permit	Irrigation	0*	40
8632-3	Bottolfson Brothers	02/03/2022	Permit	Irrigation	1.78	122.04

*Using another authorized well (No. 7472-3) to irrigate

Based on the well completion reports near the proposed diversion point for this application, the LVM aquifer is expected to be under confined conditions at the proposed well site. In a confined aquifer, drawdown from a pumping well can extend some distance from the well. The Water Management Board recognizes that putting water to beneficial use requires a certain amount of drawdown to occur. The Board has developed rules to allow water to be placed to maximum beneficial use without the necessity of maintaining artesian head pressure for domestic use. The Water Management Board defined an “adversely impacted domestic well” in ARSD 74:02:04:20(7) as:

“A well in which the pump intake was set at least 20 feet below the top of the aquifer at the time of construction or, if the aquifer is less than 20 feet thick, is as near to the bottom of the aquifer as is practical and the water level of the aquifer has declined to a level that the pump will no longer deliver sufficient water for the well owner’s needs.”

The Water Management Board considered the delivery of water by artesian head pressure versus maximum beneficial use during the issuance of Water Right No. 2313-2 for Coca-Cola Bottling Company of the Black Hills. The Board adopted the Findings of Facts and Conclusions of Law that noted the reservation of artesian head pressure for delivery of water would be inconsistent with SDCL 46-1-4 which states, “general welfare requires that the water resources of the state be put to beneficial use to the fullest extent of which they are capable...” (Water Rights, 1995). Furthermore, the Water Management Board found if increased cost or decreased production as a result of impacts on artesian head pressure by legitimate users is to be considered as an unlawful impairment, it would also conflict with SDCL 46-1-4 (Water Rights, 1995). With that in mind, some existing well owners may need to install or lower pumps depending on the specific characteristics of the LVM aquifer at their location. However, when considering the statutes (SDCL 46-1-4 and 46-6-6.1), rules (ARSD 74:02:04:20(6) and (7)), history of irrigation in the area without any recent complaints of well interference (Water Rights, 2023e), and the saturated aquifer thickness near the diversion point, any drawdown created from the diversion is not expected to cause an unlawful impairment on existing water right/permit holders or domestic users with adequate wells. Therefore, there is a reasonable probability that any interference from the proposed appropriation will not impose unlawful impairments on existing users with adequate wells.

CONCLUSIONS:

1. Water Permit Application No. 8760-3 proposes to appropriate 2.22 cfs from one well to be completed into the Lower Vermillion Missouri aquifer (approximately 120 feet deep) for irrigation of 172 acres . The site of interest is located approximately 5 miles north of Vermillion, SD in Clay County.
2. Based on observation well data and the hydrologic budget, there is a reasonable probability that unappropriated water is available from the LVM aquifer to supply the proposed appropriation.

3. There is a reasonable probability that the diversion by Water Permit Application No. 8760-3 will not unlawfully impair adequate wells for existing water rights/permits and domestic uses.



Tyler Jensen
Natural Resources Engineer I
SD DANR - Water Rights Program

Reviewed by:



Adam Mathiowetz, PE
Natural Resources Engineer IV
SD DANR -Water Rights Program

References

- Buhler, K. A. 2014. Report to the Chief Engineer on 21 Water Permit Applications from the Upper Vermillion Missouri Aquifer. SD DANR – Water Rights Program, Joe Foss Bldg. Pierre, SD.
- Hedges, L.S., Allen, J., Holly, D.E., 1985. Evaluation of Ground-Water Resources Eastern South Dakota and Upper Big Sioux River, South Dakota and Iowa, Task 7: Ground Water Recharge; United States Army Corps of Engineers Contract DACW 45-80-C-0185.
- Hedges, L.S., Burch, S.L., Iles, D.L., Barari, R.A., and Schoon, R.A. 1982. Evaluation of Ground-Water Resources Eastern South Dakota and Upper Big Sioux River, South Dakota and Iowa, Task 1: Bed rock Topography and Distribution, Task 2: Extent of Aquifers, Task 3 Ground-Water Storage, Task 4: Computerized Data Base. United States Army Corps of Engineers Contract DACW 45-80-C-0185.
- Holmes, S.L., Filipovic, D. 2015. Hydrogeologic Investigation of the Upper-Vermillion-Missouri Aquifer. Open File Report 93-UR. Akeley-Lawrence Science Center, University of South Dakota. Vermillion, SD.
- Jensen, A.R., 2000. First Occurrence of Aquifer Materials in Clay County, South Dakota. SD DANR-Geological Survey Aquifer Materials Map 1. Vermillion, SD.
- Mathiowetz, A. 2018. Report to the Chief Engineer on Water Permit Application 8335-3. Natural Resource Engineer IV, SD DANR – Water Rights Program, Joe Foss Bldg. Pierre, SD.
- Niehus, C.A., 1994. Water Resources of Lincoln and Union Counties, South Dakota. U.S. Geological Survey Water-Resources Investigations Report 93-4195. U.S. Geological Survey. Rapid City, SD.

- SDGS, 2023. South Dakota Geological Survey Lithologic Logs Database. Accessed June 26, 2023. <http://cf.sddanr.net/lithdb/>.
- Stephens, J.C., 1967. Geology and Water Resources of Clay Counties, South Dakota Part II: Water Resources. Bulletin 19. SD DANR-Geological Survey, Vermillion, SD.
- Stonesifer, J. R. 2013. Report to the Chief Engineer on Water Permit Application 7918-3. SD DANR – Water Rights Program, Joe Foss Bldg. Pierre, SD.
- Water Rights, 1995. Findings of Fact, Conclusions of Law, and Final Decision in the Matter of Water Permit Application No. 2313-2, Coca-Cola Bottling Company of the Black Hills. DANR-Water Rights Program file for Water Right No. 2313-2. Pierre, SD.
- Water Rights, 2023a. "1979-2021 Irrigation Summaries by Aquifer", SD DANR-Water Rights Program, Joe Foss Building, Pierre, SD.
- Water Rights, 2023b. Observation Well Data, SD DANR-Water Rights Program, Joe Foss Bldg, Pierre, SD.
- Water Rights, 2023c. Water Right/Permit Files, SD DANR-Water Rights Program, Joe Foss Bldg, Pierre, SD.
- Water Rights, 2023d. Well Completion Reports, SD DANR-Water Rights Program, Joe Foss Bldg, Pierre, SD.
- Water Rights, 2023e. County Files, SD DANR-Water Rights Program, Joe Foss Bldg, Pierre, SD.



**DEPARTMENT of AGRICULTURE
and NATURAL RESOURCES**

JOE FOSS BUILDING
523 E CAPITOL AVE
PIERRE SD 57501-3182
danr.sd.gov

**NOTE: TO BE SURE OF PUBLICATION ON
THE CORRECT DATES, CONTACT
THE NEWSPAPERS RIGHT AWAY.**

July 10, 2023

Bottolfson Brothers
c/o Mark Bottolfson
46003 Timber Road
Vermillion SD 57069

Dear Mr. Bottolfson:

Water Permit Application No. 8760-3 for irrigation use have been examined and found to comply with the South Dakota Water Laws and applicable rules. A notice has been sent to the PlainTalk printed at Vermillion SD (Ph # 605 624-2695) and the Daily Press & Dakotan printed at Yankton SD (Ph # 605 665-7811). You will need to contact the newspapers and authorize publication of this notice. For your information, a copy of the notice, the recommendation of the Chief Engineer and report on the application are enclosed. Please review the notice prior to publication and notify this office, if you have any corrections or questions.

Be sure to contact the above newspapers to authorize publication of your Notice and to arrange for payment. Early contact with the papers can eliminate delays. Upon receiving authorization from you, the publishers have been instructed to publish your notice. The newspapers have also been instructed to send us the Proof of Publication. We must receive Proof of Publication before action can be taken on the application.

Sincerely,

Rachel Rodriguez

Rachel Rodriguez
Water Rights Program
(605) 773-3352

enclosures

NOTE: If you plan to contest any part of the Chief Engineer's recommendation, you must file a petition pursuant to the procedures outlined in the attached notice of hearing. The Water Management Board will then consider your concerns during a hearing on the application.

NOTICE OF APPLICATION NO. 8760-3 to Appropriate Water

Notice is given that Bottolfson Brothers, c/o Mark Bottolfson, 46003 Timber Road, Vermillion SD 57069 has filed an application for a water permit to appropriate 2.22 cubic feet of water per second (cfs) from one well to be completed into the Lower Vermillion Missouri Aquifer (approximately 120 feet deep) located in the SW 1/4 NE 1/4 Section 24 for irrigation of 172 acres located in the NE 1/4, N 1/2 SE 1/4 Section 24; all in T93N-R52W. This site is located approximately 5 miles north of Vermillion SD.

Pursuant to SDCL 46-2A-2, the Chief Engineer recommends APPROVAL of Application No. 8760-3 with qualifications because 1) unappropriated water is available, 2) existing domestic water uses and water rights will not be unlawfully impaired, 3) it is a beneficial use of water, and 4) it is in the public interest as it pertains to matters within the regulatory authority of the Water Management Board. The Chief Engineer's recommendation with qualifications, the application, and staff report are available at <https://danr.sd.gov/public> or contact Ron Duvall for this information, or other information, at the Water Rights Program address provided below.

Any person interested in opposing this application or recommendation shall allege that the application, upon approval, will cause injury to the person that is unique from any injury suffered by the public in general. The injury must concern a matter either within the regulatory authority found in SDCL 46-2A-9 for approval or denial of the application, or other matter concerning the application within the regulatory authority of the board to act upon as defined by SDCL 46-2-9 and 46-2-11, or both. Any person meeting the petitioner requirements and wishing to be a party of record in a contested case hearing shall file a written petition to oppose the application with BOTH the applicant and Chief Engineer. A petition opposing the application shall be filed on a form provided by the Chief Engineer. The petition form is available online at <https://danr.sd.gov/public> or by contacting the Chief Engineer. The Chief Engineer's address is "Water Rights Program, Foss Building, 523 E Capitol, Pierre SD 57501" or call (605) 773-3352. The applicant's mailing address is given above. If contesting the Chief Engineer's recommendation, the applicant shall also file a petition. A petition filed by either an interested person or the applicant must be filed by July 31, 2023.

The petition shall include a statement describing the unique injury upon approval of the application on the petitioner, the petitioner's reasons for opposing the application, and the name and mailing address of the petitioner or the petitioner's legal counsel, if legal counsel is obtained.

Any interested person may file a comment on the application with the Chief Engineer. The comment shall be filed on a form provided by the Chief Engineer and is available online at <https://danr.sd.gov/public> or by calling (605) 773-3352 or writing the Chief Engineer at the address provided above. Filing a comment does not make the commenter a party of record or a participant in any hearing that may be held. Any comment must be filed by July 31, 2023.

If the applicant does not contest the recommendation of the Chief Engineer and no petition to oppose the application is received, the Chief Engineer shall act on the application pursuant to the recommendation with no hearing held before the Water Management Board. If a petition opposing the application or contesting the recommendation is filed, then a hearing will be scheduled, and the Water Management Board will consider this application. Notice of the hearing will be given to the applicant and any person filing a petition.

Published once at the total approximate cost of_

Rodriguez, Rachel

From: Rodriguez, Rachel
Sent: Monday, July 10, 2023 9:21 AM
To: Kelly Kronaizl
Subject: 8760-3 Bottolfson Brothers Public Notice
Attachments: 8760-3 public.short_final.docx

Attached is a notice to be published on July 21, 2023.

Bottolfson Brothers, c/o Mark Bottolfson, 46003 Timber Road, Vermillion SD 57069 (605 677-9582) has been notified to contact you to authorize publication and arrange for payment.

Please send the affidavit or return the attached Proof of Publication form ASAP to the Water Rights Program, 523 E Capitol Ave, Pierre SD 57501.

Let me know if you have questions. Please acknowledge receipt of this email.

Thank you,

Rachel Rodriguez
DANR | Program Assistant
Rachel.Rodriguez@state.sd.us



Rodriguez, Rachel

From: Rodriguez, Rachel
Sent: Monday, July 10, 2023 9:22 AM
To: Michael Pietz
Subject: 8760-3 Bottolfson Brothers Public Notice
Attachments: 8760-3 public.short_final.docx

Attached is a notice to be published on July 21, 2023.

Bottolfson Brothers, c/o Mark Bottolfson, 46003 Timber Road, Vermillion SD 57069 (605 677-9582) has been notified to contact you to authorize publication and arrange for payment.

Please send the affidavit or return the attached Proof of Publication form ASAP to the Water Rights Program, 523 E Capitol Ave, Pierre SD 57501.

Let me know if you have questions. Please acknowledge receipt of this email.

Thank you,

Rachel Rodriguez
DANR | Program Assistant
Rachel.Rodriguez@state.sd.us



RECEIVED

JUL 24 2023

OFFICE OF
WATER

AFFIDAVIT OF PUBLICATION

PLAIN TALK

MARK BOTTOLFSON
46003 TIMBER ROAD
VERMILLION SD 57069


STATE OF SOUTH DAKOTA
COUNTY OF CLAY

BETH RYE, BEING FIRST DULY SWORN ON OATH DEPOSES
AND SAYS THAT (S)HE IS THE ADVERTISING DIRECTOR OF YANKTON
MEDIA INC, A CORPORATION, THE PRINTER AND THE PUBLISHER OF THE
PLAIN TALK, A LEGAL WEEKLY NEWSPAPER PUBLISHED AND CIRCULATED
IN THE CITY OF VERMILLION, SAID COUNTY AND STATE, AND ONE OF
THE OFFICIAL NEWSPAPERS OF THE SAID COUNTY OF FACTS STATED IN
THIS AFFIDAVIT; THAT THE ANNEXED
NOTICE OF APPLICATION NO.

TAKEN FROM THE PAPER, IN WHICH IT WAS LAST PUBLISHED IN THE
NEWSPAPER ON THE 21st DAY OF July, 2023
THAT THE FULL AMOUNT OF THE FEE CHARGED FOR THE PUBLICATION
OF SAID NOTICE TO WIT \$40.00 ENSURES TO THE
BENEFITS OF THE PUBLISHER OF SAID NEWSPAPER AND THAT NO
AGREEMENT AND UNDERSTANDING FOR THE DIVISION THEREOF HAS
BEEN MADE WITH ANY OTHER PERSON, AND THAT NO PART THEREOF
HAS BEEN AGREED TO BE PAID TO ANY PERSON WHOMSOEVER.

PUBLISHED ON: 07/21/2023

FILED ON: 07/21/2023


SUBSCRIBED AND SWORN TO BEFORE ME THIS 21st DAY OF July, 2023

 8-31-27
NOTARY PUBLIC, SOUTH DAKOTA
MY COMMISSION EXPIRES 07/15/2028

Notice is given that Bottolfson Brothers, c/o Mark Bottolfson, 46003 Timber Road, Vermillion SD 57069 has filed an application for a water permit to appropriate 2.22 cubic feet of water per second (cfs) from one well to be completed into the Lower Vermillion Missouri Aquifer (approximately 120 feet deep) located in the SW 1/4 NE 1/4 Section 24 for irrigation of 172 acres located in the NE 1/4, N 1/2 SE 1/4 Section 24; all in T93N-R52W. This site is located approximately 5 miles north of Vermillion SD.

Pursuant to SDCL 46-2A-2, the Chief Engineer recommends APPROVAL of Application No. 8760-3 with qualifications because 1) unappropriated water is available, 2) existing domestic water uses and water rights will not be unlawfully impaired, 3) it is a beneficial use of water, and 4) it is in the public interest as it pertains to matters within the regulatory authority of the Water Management Board. The Chief Engineers recommendation with qualifications, the application, and staff report are available at <https://danr.sd.gov/public> or contact Ron Duvall for this information, or other information, at the Water Rights Program address provided below.

Any person interested in opposing this application or recommendation shall allege that the application, upon approval, will cause injury to the person that is unique from any injury suffered by the public in general. The injury must concern a matter either within the regulatory authority found in SDCL 46-2A-9 for approval or denial of the application, or other matter concerning the application within the regulatory authority of the board to act upon as defined by SDCL 46-2-9 and 46-2-11, or both. Any person meeting the petitioner requirements and wishing to be a party of record in a contested case hearing shall file a written petition to oppose the application with BOTH the applicant and Chief Engineer. A petition opposing the application shall be filed on a form provided by the Chief Engineer. The petition form is available online at <https://danr.sd.gov/public> or by contacting the Chief Engineer. The Chief Engineer's address is "Water Rights Program, Foss Building, 523 E Capitol, Pierre SD 57501 or call (605) 773-3352. The applicant's mailing address is given above. If contesting the Chief Engineer's recommendation, the applicant shall also file a petition. A petition filed by either an interested person or the applicant must be filed by July 31, 2023.

The petition shall include a statement describing the unique injury upon approval of the application on the petitioner, the petitioner's reasons for opposing the application, and the name and mailing address of the petitioner or the petitioner's legal counsel, if legal counsel is obtained.

Any interested person may file a comment on the application with the Chief Engineer. The comment shall be filed on a form provided by the Chief Engineer and is available online at <https://danr.sd.gov/public> or by calling (605) 773-3352 or writing the Chief Engineer at the address provided above. Filing a comment does not make the commenter a party of record or a participant in any hearing that may be held. Any comment must be filed by July 31, 2023.

If the applicant does not contest the recommendation of the Chief Engineer and no petition to oppose the application is received, the Chief Engineer shall act on the application pursuant to the recommendation with no hearing held before the Water Management Board. If a petition opposing the application or contesting the recommendation is filed, then a hearing will be scheduled, and the Water Management Board will consider this application. Notice of the hearing will be given to the applicant and any person filing a petition.

Published once at the total approximate cost of \$40.00 and can be viewed free of charge at www.sdpublicnotices.com.

Published on July 21, 2023.

AFFIDAVIT OF PUBLICATION

YANKTON DAILY PRESS AND DAKOTAN

RECEIVED

JUL 24 2023

OFFICE OF
WATER

C/O MARK BOTTOLFSO BOTTOLFSO BROTHERS
46003 TIMBER ROAD
VERMILLION SD 57069


STATE OF SOUTH DAKOTA
COUNTY OF YANKTON


KELLY HERTZ, BEING FIRST DULY SWORN ON OATH DEPOSES
AND SAYS THAT (S)HE IS THE MANAGING EDITOR OF YANKTON
MEDIA INC, A CORPORATION, THE PRINTER AND THE PUBLISHER OF THE
YANKTON DAILY PRESS AND DAKOTAN, A LEGAL DAILY NEWSPAPER
PUBLISHED AND CIRCULATED IN THE CITY OF YANKTON, SAID COUNTY
AND STATE, AND ONE OF THE OFFICIAL NEWSPAPERS OF THE SAID
COUNTY OF FACTS STATED IN THIS AFFIDAVIT; THAT THE ANNEXED
NOTICE OF APPLICATION NO.

TAKEN FROM THE PAPER, IN WHICH IT WAS LAST PUBLISHED IN THE
NEWSPAPER ON THE 21st DAY OF July, 2023
THAT THE FULL AMOUNT OF THE FEE CHARGED FOR THE PUBLICATION
OF SAID NOTICE TO WIT \$40.00 ENSURES TO THE
BENEFITS OF THE PUBLISHER OF SAID NEWSPAPER AND THAT NO
AGREEMENT AND UNDERSTANDING FOR THE DIVISION THEREOF HAS
BEEN MADE WITH ANY OTHER PERSON, AND THAT NO PART THEREOF
HAS BEEN AGREED TO BE PAID TO ANY PERSON WHOMSOEVER.

PUBLISHED ON: 07/21/2023

FILED ON: 07/21/2023


SUBSCRIBED AND SWORN TO BEFORE ME THIS 21st DAY OF July, 2023


NOTARY PUBLIC, SOUTH DAKOTA
MY COMMISSION EXPIRES 07/15/2028

5/23/29
Bm

Ad text : NOTICE OF APPLICATION NO. 8760-3 to Appropriate Water

Notice is given that Bottolfson Brothers, c/o Mark Bottolfson, 46003 Timber Road, Vermillion SD 57069 has filed an application for a water permit to appropriate 2.22 cubic feet of water per second (cfs) from one well to be completed into the Lower Vermillion Missouri Aquifer (approximately 120 feet deep) located in the SW 1/4 NE 1/4 Section 24 for irrigation of 172 acres located in the NE 1/4, N 1/2 SE 1/4 Section 24; all in T93N-R52W. This site is located approximately 5 miles north of Vermillion SD.

Pursuant to SDCL 46-2A-2, the Chief Engineer recommends APPROVAL of Application No. 8760-3 with qualifications because 1) unappropriated water is available, 2) existing domestic water uses and water rights will not be unlawfully impaired, 3) it is a beneficial use of water, and 4) it is in the public interest as it pertains to matters within the regulatory authority of the Water Management Board. The Chief Engineer's recommendation with qualifications, the application, and staff report are available at <https://danr.sd.gov/public> or contact Ron Duvall for this information, or other information, at the Water Rights Program address provided below.

Any person interested in opposing this application or recommendation shall allege that the application, upon approval, will cause injury to the person that is unique from any injury suffered by the public in general. The injury must concern a matter either within the regulatory authority found in SDCL 46-2A-9 for approval or denial of the application, or other matter concerning the application within the regulatory authority of the board to act upon as defined by SDCL 46-2-9 and 46-2-11, or both. Any person meeting the petitioner requirements and wishing to be a party of record in a contested case hearing shall file a written petition to oppose the application with BOTH the applicant and Chief Engineer. A petition opposing the application shall be filed on a form provided by the Chief Engineer. The petition form is available online at <https://danr.sd.gov/public> or by contacting the Chief Engineer. The Chief Engineer's address is "Water Rights Program, Foss Building, 523 E Capitol, Pierre SD 57501" or call (605) 773-3352. The applicant's mailing address is given above. If contesting the Chief Engineer's recommendation, the applicant shall also file a petition. A petition filed by either an interested person or the applicant must be filed by July 31, 2023.

The petition shall include a statement describing the unique injury upon approval of the application on the petitioner, the petitioner's reasons for opposing the application, and the name and mailing address of the petitioner or the petitioner's legal counsel, if legal counsel is obtained.

Any interested person may file a comment on the application with the Chief Engineer. The comment shall be filed on a form provided by the Chief Engineer and is available online at <https://danr.sd.gov/public> or by calling (605) 773-3352 or writing the Chief Engineer at the address provided above. Filing a comment does not make the commenter a party of record or a participant in any hearing that may be held. Any comment must be filed by July 31, 2023.

If the applicant does not contest the recommendation of the Chief Engineer and no petition to oppose the application is received, the Chief Engineer shall act on the application pursuant to the recommendation with no hearing held before the Water Management Board. If a petition opposing the application or contesting the recommendation is filed, then a hearing will be scheduled, and the Water Management Board will consider this application. Notice of the hearing will be given to the applicant and any person filing a petition.

Published once at the total approximate cost of \$40.00 and can be viewed free of charge at www.sdpublicnotices.com

Published July 21, 2023.

Rodriguez, Rachel

From: Rodriguez, Rachel
Sent: Monday, July 10, 2023 9:32 AM
To: 'bottolfson64@hotmail.com'
Subject: 8760-3 Bottolfson Brothers Public Notice
Attachments: 8760-3_rec.pdf; 8760-3_Ltr.pdf; 8760-3_Pub.pdf

Attached is a copy of the report, chief engineer recommendation and information regarding the public notice for your water permit application. As stated in the letter, **please contact the paper(s) as soon as possible to authorize publication and arrange for payment**. This information is also being mailed to you today.

Thank you,

Rachel Rodriguez
DANR | Program Assistant
Rachel.Rodriguez@state.sd.us





**DEPARTMENT of AGRICULTURE
and NATURAL RESOURCES**

JOE FOSS BUILDING
523 E. CAPITOL AVE
PIERRE SD 57501-3182
danr.sd.gov

AUG 31 2023

Bottolfson Brothers
c/o Mark Bottolfson
46003 Timber Road
Vermillion SD 57069

Dear Mr. Bottolfson:

Enclosed is Water Permit No. 8760-3 authorizing construction of the water diversion system and beneficial use of the water, not exceeding the limits as specified in the Water Permit.

Form 10, *Notice of Completion of Works and Application of Water to Beneficial Use*, is enclosed. Please return this completed form after you have finished the system and have put the water to beneficial use. An investigation can then be scheduled so the water license may be issued, thus completing the acquisition of a water right.

An informational sheet *Common Water Right Questions?* is also enclosed. This sheet is intended to answer some of the questions associated with obtaining and keeping a water right.

Sincerely,

Eric Gronlund, Chief Engineer
Water Rights Program
(605) 773-3352

enclosures



**DEPARTMENT of AGRICULTURE
and NATURAL RESOURCES**

JOE FOSS BUILDING
523 E. CAPITOL AVE
PIERRE SD 57501-3182
danr.sd.gov

STATE OF SOUTH DAKOTA)
) SS
COUNTY OF HUGHES)

**Affidavit of Public Notice
Posting on DANR Website**

Pursuant to SDCL § 46-2A-4, public notice of the following application was posted on the DANR web site at <https://danr.sd.gov/public>. The posted public notice is the same notice as published in the pertinent newspaper(s) and a copy of the public notice is maintained in the application file. If the application is contested, the posting is moved to the DANR contested case website at <https://danr.sd.gov/public/ContestedCase.aspx> until final action is taken on the application pursuant to SDCL § 46-2A-4.

Application No.: 8760-3

Name of Applicant: Bottolfson Brothers, Mark Bottolfson

Date of Posting: 7/18/2023

Date of Removal: 8/31/2023




Ron Duvall, Engineer III

8/31/2023


Date

Subscribed and sworn to before me, a notary public, this 31 day of August, 2023.



Notary Public - South Dakota
My commission expires: Rachel Rodriguez
My Commission Expires
May 16, 2029

(SEAL)




8760-3

SD EForm - 1621LD V1

SOUTH DAKOTA WATER WELL COMPLETION REPORT

11-02

Location SW 1/4 NE 1/4 Sec 24 Twp 93N Rg 52WCounty CLAYPlease mark well
location with an "X"

Well Completion Date

4-28-2023

1 Mile

Distance to nearest potential pollution source (septic tank, abandoned well, feed lot, etc.)?
ft. from _____ (identify source)

PROPOSED USE:

☐ Domestic/Stock ☐ Municipal ☐ Business ☒ Test holes
☐ Irrigation ☐ Industrial ☐ Institutional ☐ Monitoring well

METHOD OF DRILLING:

ROTARY

CASING DATA:

☐ Steel ☒ Plastic ☐ Other

If other describe _____

PIPEWEIGHT	DIAMETER	FROM	TO	HOLE DIAMETER
LB/FT	IN	FT	FT	5.25 IN
LB/FT	IN	FT	FT	IN
LB/FT	IN	FT	FT	IN

GROUTING DATA:

Grout Type	No. of Sacks	Grout Weight	From	To
Groutwell DF	65	Lb/gal	1 Ft	116 Ft
		Lb/gal	Ft	Ft

Describe grouting procedure

TREMME

SCREEN:

☐ Perforated pipe ☐ Manufactured

Diameter _____ Inches Length _____ Feet

Material _____

Slot Size _____ Set From _____ Feet to _____ Feet

Other information _____

WAS A PACKER OR SEAL USED?

☐ Yes ☒ No

If so, what material? _____

Describe packer(s) and location _____

DISINFECTION: Was well disinfected upon completion?

☐ Yes, How?

☒ No, Why Not?

Lab to which water

quality sample sent for analysis

TEST HOLE

Well Owner: MARK BOTTOLFFSON

Business Name: _____

Address: 46003 TIMBER RDCity, State, Zip: VERMILLION SD 57069

WELL LOG:

FORMATION	DEPTH	
	FROM	TO
TOP SOIL	0	3
GLACIAL TILL	3	15
GRAY SANDY CLAY	15	78
FINE GRAY SAND WITH CLAY	78	85
FINE TO MEDIUM SAND	85	93
FINE TO MEDIUM SAND & GRAVEL	93	116

STATIC WATER LEVEL

FEET

If flowing: closed in pressure

PSI

GPM flow

through

Inch pipe

Controlled by ☐ Valve ☐ Reducers ☐ Other

Reduced flow rate

GPM

Can well be completely shut in?

WELL TEST DATA:

☐ Pumped Describe:

☐ Bailed

☐ Other

Pumping Level Below Land Surface

_____ Ft. After _____ Hrs. pumped _____ GPM

_____ Ft. After _____ Hrs. pumped _____ GPM

If pump installed, pump rate:

GPM

REMARKS

LATITUDE: 42.860929

LONGITUDE: -96.9328

ELEVATION: 1196

RECEIVED

JUL 06 2023

OFFICE OF
WATERThis well was drilled under license # 810 and this report is true and accurate.Drilling firm: HEINE ELECTRIC & IRRIGATION, INC.

Signature of License Representative:

Signature of Well Owner or Equitable Property Holder:


Date: 7-6-23

8760-3

SD EForm - 1621LD V1

SOUTH DAKOTA WATER WELL COMPLETION REPORT

11-02

Location SW 1/4 NE 1/4 Sec 24 Twp 93N Rg 52WCounty CLAYPlease mark well
location with an "X"

Well Completion Date

11/07/2023

1 Mile

Distance to nearest potential pollution source (septic tank, abandoned well, feed lot, etc.)?
_____ ft. from _____ (identify source)

PROPOSED USE:

☐ Domestic/Stock ☐ Municipal ☐ Business ☐ Test holes
☒ Irrigation ☐ Industrial ☐ Institutional ☐ Monitoring well

METHOD OF DRILLING:

ROTARY

CASING DATA:

☐ Steel ☒ Plastic ☐ Other

 If other describe _____

PIPEWEIGHT	DIAMETER	FROM	TO	HOLE DIAMETER
94 LB/FT	16 IN	0 FT	94 FT	22 IN
_____ LB/FT	_____ IN	_____ FT	_____ FT	_____ IN
_____ LB/FT	_____ IN	_____ FT	_____ FT	_____ IN

GROUTING DATA:

Grout Type	No. of Sacks	Grout Weight	From	To
Groutwell DF	24	Lb/gal	5 Ft	65 Ft
		Lb/gal	Ft	Ft

Describe grouting procedure

TREMMIE

SCREEN:

☐ Perforated pipe ☒ Manufactured
 Diameter 16 Inches Length 20 Feet
 Material PVC
 Slot Size .050 Set From 94 Feet to 114 Feet
 Other information _____

WAS A PACKER OR SEAL USED?

☐ Yes ☒ No

If so, what material?

Describe packer(s) and location

DISINFECTION: Was well disinfected upon completion?

☒ Yes, How? HTH TABLETS
☐ No, Why Not?
 Lab to which water
 quality sample sent for analysis
Well Owner: BOTTOLFSOON BROTHERS

Business Name:

Address: 46003 TIMBER RDCity, State, Zip: VERMILLION ☒ SD ☒ 57069

WELL LOG:

FORMATION	DEPTH	
	FROM	TO
TOP SOIL	0	3
GLACIAL TILL	3	15
GRAY STICKY CLAY	15	78
FINE SAND WITH CLAY	78	85
MEDIUM SAND	85	95
MEDIUM SAND SMALL GRAVEL	95	114

STATIC WATER LEVEL 67.3 FEET

If flowing: closed in pressure _____ PSI

GPM flow _____ through _____ Inch pipe

Controlled by ☐ Valve ☐ Reducers ☐ Other _____

Reduced flow rate _____ GPM

Can well be completely shut in?

WELL TEST DATA:

☐ Pumped Describe: _____☐ Bailed☐ Other

Pumping Level Below Land Surface

_____ Ft. After _____ Hrs. pumped _____ GPM

_____ Ft. After _____ Hrs. pumped _____ GPM

If pump installed, pump rate: _____ GPM

REMARKS

LATITUDE: 42.860929

LONGITUDE: -96.9328

ELEVATION: 1196

This well was drilled under license # 810 and this report is true and accurate.Drilling firm: Heine Electric & Irrigation, Inc.

Signature of License Representative:

12-1-23

Signature of Well Owner or Equitable Property Holder:

Date: _____

**NOTICE OF COMPLETION OF WORKS AND
APPLICATION OF WATER TO BENEFICIAL USE**

Date 6-17-24

TO: Water Rights Program, DANR
523 E. Capitol
Pierre, SD 57501-3181

FROM: Bottolfson Bros, c/o Mark Bottolfson
(name)
46003 Timber Rd
(address)
Vermillion SD 57069 605-677-9582
(city, state, zip) (phone)

I have completed the construction of the water use system and I have put the water to beneficial use to the maximum extent it is going to be used.

Water Permit No. 8760-3 states that the water use system is to be constructed by
July 31, 2028 , and water is to be put to beneficial use by July 31, 2032 .
(date) (date)

The water use system was completed on 6-14-24 .
(date)

Applying the water to beneficial use was completed on 6-14-24 .
(date)

You may schedule an investigation so that the water license may be issued.


(signature)





**DEPARTMENT of AGRICULTURE
and NATURAL RESOURCES**

JOE FOSS BUILDING
523 E. CAPITOL AVE
PIERRE SD 57501-3182
danr.sd.gov

June 24, 2024

8760-3

Bottolfson Bros
c/o Mark Bottolfson
46003 Timber Rd
Vermillion SD 57069

Dear Mr. Bottolfson:

I am writing to acknowledge receipt of the "Notice of Completion of Works" form that you sent in to let us know that you are completed with your water use system, authorized by Permit No. 8760-3.

The system is now ready for inspection. Inspections are done on a county-by-county basis as staff time permits. You have done everything you need to do and the intervening time between the completion of your project and the staff inspection has no bearing on your water permit.

Someone from our office will contact you prior to the inspection to set up a time that is convenient for you. If you have any questions, please contact me.

Sincerely,

Amanda Dewell
Water Rights Program
(605) 773-3352
email: Amanda.Dewell@state.sd.us

Report of Examination of Works and/or Application of Water to Beneficial Use
For Permit No. 8760-3

I have this day, November 6, 2024, made a thorough examination of the water use systems owned by Bottolfson Brothers, c/o Mark Bottolfson, 46003 Timber Road, Vermillion, SD 57069, holder of Permit No. 8760-3, bearing the priority date of May 8, 2023. This permit authorizes the diversion of 2.22 cubic feet per second of the waters of groundwater (Lower Vermillion Missouri Aquifer) authorizing the irrigation of 172 acres located in Clay County.

Inspection contacts: Mark Bottolfson

A. Works used to divert the water:

Well Information

- 1) Well Drilling Firm: Heine Electric & Irrigation, Inc.
- 2) No. of Wells: 1
- 3) Depth(s): 114 feet
- 4) Well log is available: Yes

Casing:

- 1) Diameter: 16 inches
- 2) Length: 94 feet
- 3) Type: Plastic

Screen:

- 1) Diameter: 16 inches
- 2) Length: 20 feet
- 3) Type: PVC Manufactured
- 4) Static water level: 67.3 feet

Pump:

- 1) Make: AY McDonald
- 2) Model: Unknown
- 3) Capacity: 1,100 gpm

Motor:

- 1) Make: Franklin
- 2) Model No.: Unknown
- 3) Horsepower rating: 60 hp

B. Works used to transport water to place of use:

- 1) Type: Aluminum Size: 8 inches Length: 20 feet

C. Works used to apply water to beneficial use:

Center Pivot:

- 1) Make: Valley
- 2) Overall length: 1,959 feet
- 3) Number of towers: 11
- 4) End gun: Yes Range: 96 feet
- 5) Capacity: 1,000 gpm

Chemigation Equipment:

- 1) Does chemigate: No

D. Compliance with Permit Requirements:

- 1) Permit qualifications being abided by: No
- 2) Irrigation Questionnaires checked to determine if permit owner started irrigation by the end of construction period: New in 2024
- 3) Exceptions to compliance are: The pump can produce more than authorized by the permit.

E. Condition and Location:

- 1) The system is in good condition with the point(s) of diversion located as follows:
The well is 1,980 feet south and 2,210 feet west of the northeast corner of Section 24-T93N-R52W (Latitude 42.86097, Longitude -96.93271– SW1/4 of the NE1/4).
- 2) The works are capable of diverting and conveying to the places of use 2.45 cu. ft. per second of water from the well which is to be used for irrigation purposes. Water has been put to beneficial use to the maximum extent as follows: All in

Section 24-T93N-R52W

<u>NW1/4NE1/4</u>	<u>35 acres</u>
<u>NE1/4NE1/4</u>	<u>19 acres</u>
<u>SW1/4NE1/4</u>	<u>30 acres</u>
<u>SE1/4NE1/4</u>	<u>34 acres</u>
<u>NW1/4SE1/4</u>	<u>36 acres</u>
<u>NE1/4SE1/4</u>	<u>18 acres</u>

comprising a total of 172 acres of land and the license should be issued for 2.22 cfs.


- 3) All structures, wells and lands on map: Yes

F. Comments or other permit(s) associated with the project: The pump and motor information was obtained from Heine Electric and Irrigation, Inc. The pump is capable of putting out 2.45 cfs, but the pivot is nozzled for 1,000 cfs.

Keith DeJong, PE Ret.
Water Rights Inspector
DANR, Water Rights Program

Date report completed: November 13, 2024

Water Permit No. 8760-3



0 330 660 1,320 1,980 2,640
Feet
SCALE



Keith DeJong
Keith DeJong, PE Ret.
Staff Engineer
November 6, 2024



**DEPARTMENT of AGRICULTURE
and NATURAL RESOURCES**

JOE FOSS BUILDING
523 E. CAPITOL AVE
PIERRE SD 57501-3182
danr.sd.gov

APR 30 2025

Bottolfson Brothers
c/o Mark Bottolfson
46003 Timber Road
Vermillion, SD 57069

No. 8760-3

Dear Mr. Bottolfson:

Enclosed is Water License No. 8760-3. This is the final water right document completing your process of obtaining a Water Right. Included with your license is a map prepared by the staff engineer who conducted the field investigation.

For your information SDCL 46-6-27 requires that if in the future, the owner of an existing well, constructs a replacement well and does not plan to use the old well, the old well is considered abandoned and must be plugged. Also, any well that is being used or is not considered abandoned must be valved and controlled, if flowing, or sealed and capped so that no leaking occurs either underground or at the surface.

So long as you use the water beneficially, as stated in the Water License, State Water Laws provide that you have a continuing right to use the water. If you have any questions, please contact our office.

Sincerely,

Mark Mayer, PE
Director of Office of Water
(605) 773-3352

enclosures

**STATE OF SOUTH DAKOTA
WATER LICENSE NO. 8760-3**

(1) Bottolfson Brothers, 46003 Timber Road, Vermillion, SD 57069, made Application No. 8760-3, May 8, 2023, for a water permit to divert 2.22 cubic feet of water per second from groundwater, one well (Lower Vermillion Missouri Aquifer), Clay County, South Dakota for irrigation purposes. Permit No. 8760-3, with a priority date of May 8, 2023, was approved July 31, 2023, and issued to the applicant for diversion of water with construction of the described water supply system to be completed on or before July 31, 2028, and for the application to beneficial use of water on or before July 31, 2032.

The permit holder submitted a Notice of Completion of Works and Application of Water to Beneficial Use form on June 21, 2024. The Notice stated the diversion system was completed on June 14, 2024 and the water was placed to beneficial use on June 14, 2024.

(2) It is certified that the permit holder has complied with the provisions of South Dakota State Law relating to completion of the construction of the water supply system and is entitled to divert 2.22 cubic feet of water per second for beneficial use. The location of the diversion point is:

- 1,980 feet S and 2,210 feet W from the NE corner Section 24, T93N, R52W (SW $\frac{1}{4}$ NE $\frac{1}{4}$)
(Latitude 42.86097 and Longitude -96.93271)

(3) The amount of appropriation may not exceed 2 acre-feet annually for each acre of land to which water is actually and beneficially applied for irrigation. The water is to be used during the following described annual period: May 1 – September 30.

(4) The permit holder has complied with the provisions of South Dakota State Law relating to the application of water to beneficial use to irrigate to following land:

Section 24, T93N, R52W
NE $\frac{1}{4}$ NE $\frac{1}{4}$ - 19 acres
NW $\frac{1}{4}$ NE $\frac{1}{4}$ - 35 acres
SW $\frac{1}{4}$ NE $\frac{1}{4}$ - 30 acres
SE $\frac{1}{4}$ NE $\frac{1}{4}$ - 34 acres
NE $\frac{1}{4}$ SE $\frac{1}{4}$ - 18 acres
NW $\frac{1}{4}$ SE $\frac{1}{4}$ - 36 acres
Total – 172 acres

(5) Pursuant to South Dakota Water Law 46-5-30.1 Bottolfson Brothers, the holder and/or owner of Water Right No. 8760-3 is issued a license to appropriate water, the right to use 2.22 cubic feet of water per second from groundwater, one well (Lower Vermillion Missouri Aquifer), with a priority date of May 8, 2023, from the location specified in (2) of this license for irrigation purposes.

This license is subject to South Dakota Water Law, any limitations or conditions listed in Water Right No. 8760-3 and subject to the following qualifications:

1. The well approved under Water Permit No. 8760-3 is located near domestic wells and other wells which may obtain water from the same aquifer. Water withdrawals shall be controlled so there is not a reduction of needed water supplies in adequate domestic wells or in adequate wells having prior water rights.

2. The well authorized by Permit No. 8760-3 shall be constructed by a licensed well driller and construction of the well and installation of the pump shall comply with Water Management Board Well Construction Rules, Chapter 74:02:04 with the well casing pressure grouted (bottom to top) pursuant to Section 74:02:04:28. *(The well was drilled in 2023 by Heine Electric & Irrigation Inc. A copy of the well completion report is on file with the Water Rights Program.)*

3. This Permit is approved subject to the irrigation water use questionnaire being submitted each year.

Mark Mayer

Mark Mayer, PE
Director of Office of Water

4/30/25

date

